



बड़ौदा यू.पी.बैंक
Baroda U.P. Bank

RO/MAU/ P&E/2021-22/502

DATE: 12.11.2021

TENDER FOR FURNISHING OF REGIONAL OFFICE- MAU

Baroda UP Bank, Regional Office, Ghazipur Tiraha near Grihasth Plaza, Mau invites sealed tender for furnishing for our REGIONAL OFFICE MAU.

- 1) Tender Issuing Date :12.11.2021
- 2) Last Date of Submission of Tender :07.12.2021 at 2:00PM
- 3) Date of opening of tender :08.12.2021 at 2:00 PM
- 4) Tender to be addressed to :

The Regional Manager
Baroda U P Bank,
Regional office-Mau
Ghazipur Tiraha near Grihasth Plaza
Mau-275101 (UP)

Terms & Condition of tender:

- Rates should be quoted on the space provided in the **annexure attached only**. No other sheet /form should be used for quoting rates.
- The competent Authority (Bank) does not bind themselves to accept the lowest or to give any reasons for its decision of acceptance or rejection of tenders.
- Incomplete in any respect or conditional tender shall liable to be rejected.

Other conditions

- The registration number of the firm along with GST no. allotted by the authorities must be submitted.
- PAN NUMBER of the firm allotted by the income tax authorities should be submitted (without which the vendor's bid would become invalid and shall be liable to be reject).
- Conditional tenders shall not be accepted on any ground and shall be rejected straight.
- Any deviation of the conditions given by the purchaser will not be accepted and bid will be rejected without assigning any reasons.
- If any clarification is required the same should be obtained before submitting the bid.
- The Entire document must be signed with the seal and attached as a mark of acceptance of the terms & conditions.
- BUPB reserves the right to accept or reject any bid whole or in parts without assigning any reason thereof.
- Bank's decision will be final and no correspondence will be entertained in this regard.
- In case of delay in submission/non submission of bids, Bank will not assume any responsibility.

क्षेत्रीय कार्यालय, नरई बाँध, गृहस्थ प्लाजा के पास, मऊ-275001, दूरभाष: 0547-2229000

Regional Office, Narae Bandh, Near Grihasth Plaza, Mau-275001, Telephone: 0547-2229000

e-mail: ROMAUK@barodauprb.co.in

sl



बड़ौदा यू.पी.बैंक
Baroda U.P. Bank

- Bank may reject any or all quotations without assigning any reason.

Tender Submission:

Submission of tender in sealed envelope super scribing "TENDERS FOR FURNISHING OF REGIONAL OFFICE MAU" addressed to Baroda UP Bank, Regional Office- Mau, Ghazipur Tiraha near Grihasth Plaza, Mau; Complete in all respect by 2:00PM, Dated 07.12.2021. Tenders received after, shall not be entertained. Tender must be submitted by hand / Registered post.

Evaluation of tender:

Quoting incredibly low value of items with the view of subverting the tender process shall be rejected straight away.

Yours Faithfully,

(P.K Sinha)

Regional Manager (Inchg.)

क्षेत्रीय कार्यालय, नरई बाँध, गृहस्थ प्लाजा के पास, मऊ-275001, दूरभाष: 0547-2229000

Regional Office, Narae Bandh, Near Grihasth Plaza, Mau-275001, Telephone: 0547-2229000

e-mail: ROMAUK@barodauprrb.co.in

REF NO.:BA/BUPB/MAU/2021

Date 12.11.2021

**DETAILED ESTIMATE / SPECIFICATION FOR BILL OF QUANTITIES OF FURNISHING WORK OF
BARODA U.P. BANK AT REGIONAL OFFICE, MAU**

S.NO.	PARTICULAR OF WORK	QTY.	UNIT	RATE	AMOUNT
1	<u>FALSE CEILING:</u> <u>DESIGNER ARMSTRONG CEILING/GEPSUM BOARD CEILING WITH COPE.</u> Providing and fixing ,ARMSTRONG Make, false ceiling with provision of Cassette AC and Electrical fixture, using DUNE RH99 acoustical tiles of size 600 mm x 600 mm x 15mm using SILHOUETTEMICROLOOK suspension system, consisting of main runner- with stitching Cross Tee - stitching Cross Tee -Wall angle These members are Hot Dipped Galvanised steel. FRAME WORK.-Main runner spaced at 1200mm centre fixed to soffit by quick hanger-Hook (double hooks) at 1200mm distance. First and last hanger should not be at a distance more than 450mm from the adjacent wall.1200mm cross Tee to be interlocked between main runners at 600mm centre From 1200x600 modules. 600mmx600mm module to be framed by fixing 600mm crosses Tee between centres of 1200mm cross Tee. Wall angle to be secured to wall at 450mm centres. Spot lights and other luminaries: never loathe tiles directly, Spot lights and other luminaries should be independently hung Or use 6mm Plywood of tile size of Patters on the back to transfer the load on to the grid system.	3000	SFT		
2	<u>PILLAR PANELING</u> Providing and Fixing of frame work on Pillars & Walls with Ply & Mica as per Partition Given above with same colour code complete in all respect up to ceiling height.	400	SFT		
3	<u>FULL HT. PARTITION</u> Providing & Erection of partly glazed laminated partition with door spring up to ceiling high made out of 2"x1 1/2" well-seasoned Kael wood with anti-termite treatment under framing at 2'-0" c/c in both direction covered with 6 mm th .commercial ply and 1 mm. thick laminates on both side. All free top / end surface shall have teak wood molds with Melamine polished. The rate of glass including.	1190	SFT		
4	<u>LOW HT. PARTITION (3' + 1'-6")</u> Providing & Erection of partly glazed (each glass 12mm, With Dhār polished and round corner on top of the partition as per architect design) laminated partition up to	415	SFT		



	4'-0" high made out of 2"x1 1/2" well seasoned kail wood with anti termite treatment under framing at 2'-0" c/c in both direction covered with 6 mm th. Commercial ply and 1 mm. thick laminate on both sides. All free top / end surface of wooden partition shall have teak wood molds with Melamine polished. The rate of glass including.				
5	ENTRANCE DOOR WITH 12 MM THICK TOUGHENED GLASS Providing and fixing double door of toughened glass of 12 mm thick with all accessories with Colored Logo of Baroda UP Bank in center of both doors.	55	SFT		
6	WORK STATIONS Providing and erection on site wooden work station as per design. Height of counter will be 2'-6" high and writing desk will be 2'-0" deep and length will be 3'-6". It should be made out of block board 19 mm. thick and 1 mm. thick laminates (as per shade approved by the color code of bank) the inside desk will be provided with 16" wide 5" high & 24" deep drawers with telescopic channel have lock of approved make. All the exposed edge of block board will be provided with 38mm. thick teak wood lapping duly melamine polished with Keyboard and C.P.U. platform at the foot rest and provision of wire manager complete in all respect.	81	RFT		
7	BACK AND SIDE CABINET Providing and placing in position SIDE/ BACK Table units made of 19 mm th. commercial finish board with 1 mm th. Laminate finish, along with 3 no. of drawers, & openable pallas in cabinets, shelves & locks as per detail (a) size: 4'0" (L) x 1'3" (W) x 2'6" (H)	75	SFT		
8	PARTITION IN BETWEEN TWO ROWS OF WORKSTATIONS Providing and fixing of wooden partition of 1'-6" ht. same as Low Ht. Partition with cellotex Board and frame separately for each table with Colored velvet cloth with Pin complete in all respect. Color of velvet cloth is as per Architect advice.	80	SFT		
9	BOARD IN FRONT OF WORKSTATIONS Same as Item no. 8 only with Cellotex Board and velvet cloth with pin.	70	SFT		
10	D.R.M.TABLE Providing and placing in position, table made of 19 MM. BWR, termite proof, borer proof commercial finish with top, front, and sides finished in 1 MM th., on one side with necessary mouldings, lippings in TK. Wood. Laminate is to be fixed in book matching fashion, as per the design. TK. Wood sections to be provided in the table as per the requirement & design, storage unit shall consist of drawers, and open able shutters. keyboard drawers. space for keeping C.P.U. and suitable fascia to be provided as per the design. Drawers shall consist of 12 MM thk. Commercial finish ply for bottom sides & back and 19 MM thk. Commercial finish board with specified LAMINATE on the front side, the fascia of drawers to be made in panelled fashion using 12 mm ply to create level differences and using necessary mouldings on the tucks as per the detail. Drawers to slide on telescopic sliding	1	NO.		



8/

	mechanism. All exposed edges of ply/ board to be finished in 3 mm thk. Tk. Wood lipping. All the units to be provided with necessary hardware i.e. handles, knobs, multipurpose locks (Godrej make, pais separately). sliding mechanism of magnetic catchers, brass piano hinges, PVC ferrules, etc. All hardware to approved by the Architect and to be of superior brass / S.S. finish & lacquered. All exposed wooden surfaces to be polished in high class French spirit polish in reddish/ rosewood/ red cedar tint as per approved sample and finished in 2 coats of melamine in matt finish. All unexposed areas to be wax polished /enamel painted & wood primer with Glass Table Top full size 12mm all complete as per details in neat fashion. (a) size: 6'-0" (L) x 3'-0" (W) x 2'-6" (H)				
11	OFFICERS TABLE: Same as Item no.10 with (b) size: 5'-0"(L)x 2'-6"(W)x 2'-6"(H)	3	Nos.		
12	TABLE FOR MEETING HALL: Same as Item no.10 with (c)Size: 28'-0"(L)x 4'-0"(W)x 2'-6"(H)	112	SFT		
13	DINING TABLE FOR PANTRY: (d)Size: 5'-0"x 2'-6" x2'-6"	1	No.		
14	SOFA, CENTRE TABLE AND CORNER TABLES IN VISITOR'S LOBBY: As per Drawing	0	JOB		
15	WOODEN CUPBOARD ON WALL UPTO FALSE CEILING: Same as Item no. 7	250	SFT		
16	EXTERNAL WALL PANELING OF ACP SHEET AND SHUTTER BOX WITH BANK COLORED CODE AND LOGO IN CENTER OF WALL: ACP sheet make Alstone/Alstar thickness 3mm with Aluminium frame complete in all respect.	0	SFT		
17	RCC RACK WITH SINK : Casting of RCC RACK 2'-0" WIDE with Granite on top at 2'-6" ht. and provision of sink and Tap in pantry. Providing Tiles on walls above rack up to false ceiling and cabinet of 2' ht and 2' deep above rack, at 5'-0" ht. complete in all respect.	1	JOB		
18	O.B.D. PAINTING ON WALL & CEILING: After preparation of wall surface by wall care putty for smoothing the surface two coats of O.B.D. paints as per required including scratching & sand papering of existing wall / distemper etc. Two coats of primer & two coats of paints on it as per shade approved by the architect.	100	SFT		
19	DEMOLITION OF OLD WORK	1	JOB		
20	EACHED GLASS PARTITION 12MM THICK OVER TOP OF WORK STATIONS	200	SFT		
21	FLUSH DOOR: Supply & Fixing in position overall 32mm thick solid core hot pressed Flush Door finished with 1.0mm thick laminate of approved shade and Quality. Necessary Cutting-in Door and fixing glass (8mm) as shown in the drawing including cost of hardware fittings e.g. Godrej night latch, Mortise lock, Hinges, Door closure, Handle etc. (Manager cabin, Cash cabin, Wicket Gate etc.)	150	SFT		



22	REPAIR OF OLD TABLE: Providing and fixing of Ply and Mica in new colour code of R.M. table and side cabinet.	1	JOB		
23	VERTICAL BLINDS IN R.M. CHAMBER	1	JOB		
TOTAL AMOUNT					

(CONTRACTOR'S SEAL)

(U.C. SRIVASTAVA)
PANEL ARCHITECT

LIST OF APPROVED MATERIAL & MAKE

1. BOARD/PLY	: CENTURY, GREEN.
2. LAMINATE	: AICA SUNMICA, CENTURY
3. GLASS	: TATA FLOT GLASS, MODI, ASAHI
4. ADHESIVE	: FEVICOL, JEEVANJOR
5. LOCK / NIGHT LATCH	: GODREJ, LINK.
6. FIXTURE/FITTING	: EARL, BIIHARI, ELIBE
7. WALL CARE PUTTY / P.O.P.	: BIRLA, J.K. PUTTY
8. PAINT	: ASIAN, NEROLAC, BERGER
9. FLOOR SPRING	: GODERJ.


NOTE:

1. DETAILS OF COLOUR OF LAMINATION AND ACP SHEET IS AS PER COLOUR CODE OF BARODA UP BANK.

DATE:

(U.C. SRIVASTAVA)

PANEL ARCHITECT
BARODA UP BANK



**BILL OF QUANTITY FOR ELECTRICAL WIRING WORK FOR BARODA UP BANK OF
REGIONAL OFFICE, MAU**

S.No.	Description of Items	Qty.	Unit	Rate	Amount
1-	Supply & Fixing of FP MCCB 250Amp 35ka with Enclosure near Energy Meter before Main Panel.	1	Set.		
2-	Supply & Fixing of TPN MCB DB 4way Double Door with 63Amp FP RCCB 300ma as Incommer and suitable load rating SPMCBs as per requirment for Light/Fan. UPS & AC.	3	Nos.		
3-	Supply & Fixing of SPN MCB DB 12way Double Door with 40Amp DP RCCB 300ma as Incommer and suitable load rating SPMCBs as per requirment for Light/Fan. UPS & AC.	5	Nos.		
4-	By reusing old materials & Drawing Circuit line by (2x6+1x2.5)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with Fitted Conciled or Open as per site instruction by Architect for Sub Mains Panel to TPN &	118	Mtr.		
5-	By reusing old materials & Drawing Circuit line by (2x4+1x2.5)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site instruction by Architect for UPS, SPNDB & AC.	490	Mtr.		
6-	By reusing old materials & Drawing Circuit line by (2x2.5+1x1)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site instruction by Architect for All Circuit wiring.	480	Mtr.		
7-	By reusing old materials & Drawing Circuit line by (2x1.5+1x1)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site instruction by Architect for PC Circuit wiring.	570	Mtr.		
8-	Supply & Fixing 63Amp DP MCB with Enclosure for UPS Incoming and Outgoing.	2	Nos.		



82

S.No.	Discription of Items	Qty.	Unit	Rate	Amount
	B/F- Before Page---			Rs.	
9-	Light Fan Point Wiring by 1.5 Sq.mm Copper wire with all accessories like Switch, Socket, Top & Cover Plate as per Following---				
a-	Single Point controlled by Single Switch.	90	Point.		
b-	Double Point controlled by Single Switch.	20	Point.		
c-	Socket 6Amp Point controlled by Single Switch.	12	Point.		
d-	Call Bell controlled by Bel Push.	2	Nos.		
10-	Fan Point controlled by Electronic Regulator & Switch.	8	Nos.		
11-	Supply & Fixing for Raw Power 6/16Amp Socket with Switch.	12	Nos.		
12-	Supply & Fixing for PC Terminal Power Board 4way 6Amp Socket with Switch.	40	Set.		
13-	Supply & Fixing Air-conditioner Starter with 20Amp SPN MCB and Socket including Power Top.	6	Nos.		
14-	Earthing Work: Supply & Fixing Maintenance Free Electrode Earth with Backfil compound chemical Bag resistance shuld be less than 2.0 Ohms specification as per IS 3043/1987 complete in all respects.	6	Job.		
15-	By reusing old materials & Laying 10Sq.mm Copper Wire for Earthing Circuit Earth Place to UPS, Main Panel & all DBs.	120	Mtr.		
16-	Supply & Drawing LAN Cabling by CAT-6 in PVC Conduit Pipe.	600	Mtr.		
17-	Re- fixing of Data Info-Rack 19" 9U complete in all respects.	2	Nos.		
18-	Supply & Fixing Networking Information Outlet Box (I.O. Box) complete in all respects.	40	Nos.		
19-	Supply & Fixing RJ-45 connector at LAN Cable one end complete in all respects.	40	Nos.		



S.No.	Description of Items	Qty.	Unit	Rate	Amount
	B/F- Before Page---			Rs.	
20-	Re-fixing Fast Ethernet Switch 24 Port as per Advice by Architect.	2	Nos.		
21-	Supply & Fixing Patch Cord (CAT-6) 1Yard.	20	Nos.		
22-	Supply & Fixing Patch Cord (CAT-6) 2Yard.	8	Nos.		
23-	Supply & Fixing LED Square Panel 2'x2' 36W.	20	Nos.		
24-	Supply & Fixing LED Round Panel 12Watts.	30	Nos.		
25-	Supply & Fixing LED Batten Fitting 18Watts.	6	Nos.		
26-	Supply & Fixing Wall Fan 400mm.	20	Nos.		
27-	Re-fixing of Ceiling Fan 1200mm.	8	Nos.		
28-	Refixing of Exhaust Fan 300mm.	6	Nos.		
29-	Refixing of old WALL FAN after maintaining in new and good condition.	15	Nos.		
30-	Refixing of old SPLIT AC(6 Nos.) and Window AC(2 Nos.) after maintaining it in good condition.	1	Job		

Total Rs.

List of Approved Make:-

Copper Wire FRLS Grade	: Finolex/ Polycab/ Havell's/ HCL/ RR Kable.
Electric Cable	: Havell's/ Polycab/ Gloster.
ELCB, MCCB & RCCB	: L&T/ Siemens/ GE/ Havell's/ ABB/ HPL/ Leagrand.
MCBs, DBs, SFUs	: L&T/ Siemens/ GE/ Havell's/ ABB/ HPL/ Leagrand.
Modular Switch, Sockets	: Anchor Roma/ Crabtree/ MK/ Polycab.
Earthing for Bldg. & UPS	: Earth Electrode IS:3043-1978 Chemical Earthing.
PVC Conduit Pipe	: AKG/ Precision/ Polycab/ Asian.
Telephone & Data Cable	: Digilink/ Finolex/ Polycab/ Havell's/ HCL/ RR Kable.
Lugs	: Dowells/ Jainson or Equivelents.
Metal Clad Sockets	: Siemens/ MDS or Equivelents.

Date:

(U.C.SRIVASTAVA)
Panel Architect
(Baroda UP Bank)

(CONTRACTOR'S SEAL)

