

बड़ौदा यू पी बैंक
 क्षेत्रीय कार्यालय फ़तेहपुर
 2 A, गौतम नगर
 आईटीआई रोड,
 फ़तेहपुर-212601

(INTERIOR FURNISHING, ELECTRICAL, UPS, DATA CABELING
 WORKS, ONLY VENDORS EMPANELLED WITH
 BARODA U. P. BANK HEAD OFFICE, GORAKHPUR
 CAN APPLY)

EMPANELMENT OF VENDORS
 FOR

“INTERIOR FURNISHING WORK, ELECTRICAL, UPS
 & DATA CABELING WORKS AT OFFICE/BRANCHES DISTT. FATEHPUR”

निविदाएं जारी करना 15.01.2024 से 05.02.2024 तक
 जमा करने की अंतिम तिथि 05.02.2024 अपराह्न 05.00 बजे तक
 निविदा खुलने की तिथि 06.02.2024 समय प्रातः 11.30 बजे
 (निविदाएं पैनल वेंडर या उनके अधिकृत प्रतिनिधियों की उपस्थिति में खोली जाएंगी)

निविदाएं बैंक की वेबसाइट www.barodaupbank.in/tender से डाउनलोड की जा सकती हैं या
 निम्नलिखित पते से प्राप्त की जा सकती हैं और दी गई तारीख तक जमा की जानी चाहिए (हमारे
 बैंक के पैनल में शामिल फर्निशिंग और इलेक्ट्रिकल विक्रेता आवेदन कर सकते हैं)

निविदा संग्रहण/प्रस्तुति का स्थान:

बड़ौदा यू पी बैंक
 क्षेत्रीय कार्यालय फ़तेहपुर
 2 A, गौतम नगर
 आईटीआई रोड,
 फ़तेहपुर-212601

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05180-221213 ,
 email: cofare@barodauprb.co.in

टेंडर संख्या: RO/FATEH/04/P&E/2023-24/174



निविदा हेतु सूचना

Sub: - Interior Furnishing, Electrical, UPS & Data works for Baroda UP Bank at Office/Branches Distt. Fatehpur.

- 1) बड़ीदा यू.पी. क्षेत्रीय कार्यालय फतेहपुर को अपने क्षेत्र की विभिन्न शाखाओं हेतु इंटीरियर फर्निशिंग, इलेक्ट्रिकल, यू.पी.एस., डेटा केबलिंग कार्य के निष्पादन के लिए हमारी बैंक में सूचीबद्ध ठेकेदारों से निर्धारित प्रारूप में मुहरबंद, आइटम दर, निविदाएं निम्नलिखित विवरण के अनुसार आमंत्रित की जाती हैं:-

कार्य का नाम:	इंटीरियर फर्निशिंग, इलेक्ट्रिकल, यू.पी.एस. और डेटा डेटा केबलिंग
समापन की अवधि:	प्रत्येक कार्य आदेश के लिए 3 (तीन) सप्ताह
निविदा की वैधता :	120 दिन
निविदा जारी करने की तिथि :	15.01.2024 से,
जमा करने की अंतिम तिथि:	05.02.2024 को सांय 05.00 बजे तक
खोलने की तिथि एवं समय :	प्रातः 11.30 बजे 06.02.2024 को
दरों की वैधता:	<u>दो निर्दिष्ट खोलने की तारीख से कम से कम एक वर्ष के लिए वैध होगी</u> <u>आवश्यकता होने पर बैंक (क्षेत्रीय कार्यालय) ऑर्डर देगा</u>

- निविदा वस्तावेज हमारे बैंक की वेबसाइट www.barodaupbank.in/tender से डाउनलोड किया जा सकता है या बड़ीदा यू.पी. बैंक, क्षेत्रीय कार्यालय-2 A गौतम नगर आई.टी.आई. फतेहपुर से प्राप्त किया जा सकता है और मूल प्रति, विधिवत मुहर लगी और उसी कार्यालय में जमा/कुरियर/पंजीकृत डाक से जमा की जानी चाहिए।
- अनुबंध के तहत मद दरों में, अनुबंध में वर्णित सभी मामलों में सभी कार्यों के पूर्ण, अंतिम और संपूर्ण समापन शामिल हैं। ठेकेदार को कार्य की सभी वस्तुओं के लिए वस्तु दरें उद्धृत (quote) करनी होंगी। निविदाएं ठेका एजेंसियों या उनके अधिकृत प्रतिनिधियों और क्षेत्रीय कार्यालय समिति के सदस्य की उपस्थिति में खोली जाएगी।
- निविदाएं एक सीलबंद लिफाफे में प्रस्तुत की जाएंगी। लिफाफे के ऊपर Financial Bid लिखा जाएगा, इसमें निविदा का Volume- 1 होगा।
- आवश्यक EMD का अनुपालन करने वाले ठेकेदारों का ही लिफाफा नियत तारीख और समय पर खोला जाएगा।
- निविदाएं एक सीलबंद लिफाफे में जमा की जानी हैं, जिस पर " Interior Furnishing, Electrical, UPS & Data works for Baroda UP Bank at Office/Branches Distt. Fatehpur." लिखा हुआ होगा।
- निविदाकर्ता को दरों को भरने के लिए केवल जारी किए गए निविदा प्रपत्रों का ही उपयोग करना होगा। पत्र, टेलीग्राम/टैलेक्स द्वारा दी गयी निविदा की सूचना स्वीकार्य नहीं होगी।
- निविदाकर्ताओं को सलाह दी जाती है कि वे निविदा दस्तावेजों, कार्य की वस्तु या किसी भी संबंध में कोई बदलाव/संशोधन न करें। इसका उल्लंघन करने पर निविदा अस्वीकृत कर दी जाएगी।
- डाक वितरण के मामले में, निविदाकर्ता को यह सुनिश्चित करना होगा कि निविदा नियत तिथि और समय से पहले पहुंच जाय। बैंक डाक वितरण में क्षति और निविदा की प्राप्ति में देरी, यदि कोई हो या किसी विशेष व्यक्ति द्वारा भेजा गया हो, के लिए जिम्मेदार नहीं होगा। निर्धारित समयवधि उपरोक्त प्राप्त निविदा अस्वीकार कर दी जाएगी।

Signature & Seal of the Contractor

Regional Office : JA Gaudas Nagar Fatehpur (U.P.) Tel. : 05140-221213 ,
e-mail : rofate@barodauprb,co.in

टेंडर संख्या: RO/FATEH/04/P&E/2023-24/174



- 10) निविदा दस्तावेजों के प्रत्येक पृष्ठ पर निविदा प्रस्तुत करने वाले व्यक्ति या व्यक्तियों द्वारा हस्ताक्षर किए जाने चाहिए, जो यह दर्शाता हो कि वे अनुबंध की सामान्य और विशेष शर्तों, विशिष्टताओं आदि से परिचित हैं, जैसा कि निर्धारित किया गया है। बिना हस्ताक्षरित किसी भी दस्तावेज के साथ कोई भी निविदा अस्वीकार कर दी जाएगी।
- 11) प्रचलित बाजार दरों से अत्यधिक विचलन होने पर निविदा निरस्त करने का अधिकार बैंक सुरक्षित रखता है।
- 12) उपरोक्त निर्धारित समय के बाद प्राप्त निविदा पर कोई विचार नहीं किया जाएगा और निविदा जमा करने के लिए कोई विस्तार की अनुमति नहीं दी जाएगी। बढ़ीदा यू.पी. बैंक न्यूनतम निविदा को स्वीकार करने के लिए बाध्य नहीं होगा और बिना कोई कारण बताए, किसी भी या सभी निविदाओं को स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता है।
- 13) निविदाएं आमंत्रित करने वाला यह नोटिस, निविदा की शर्तों और निविदा का विधिवत पूरा किया गया फॉर्म आदि सफल निविदाकर्ता द्वारा बैंक के साथ निष्पादित किए जाने वाले समझौते का हिस्सा होगा।
- 14) रेट केवल Annexure-I में दिए गए स्थान पर ही लिखी जानी चाहिए। रेट लिखने के लिए किसी अन्य शीट/फॉर्म का उपयोग नहीं किया जाना चाहिए।
- 15) Annexure-I में उल्लिखित प्रत्येक Item के सामने रेट लिखना आवश्यक है। किसी भी Item का रेट ना लिखने की स्थिति में संबंधित वेडर की निविदा निरस्त कर दी जाएगी।
- 16) बैंक में empanelled वेडरों के ही प्रस्ताव/रेट स्वीकार किए जायेंगे।
- 17) सक्षम प्राधिकारी (बैंक) निविदाओं को स्वीकार करने या अस्वीकार करने के अपने निर्णय के लिए न्यूनतम राशि स्वीकार करने या कोई कारण बताने के लिए बाध्य नहीं है।
- 18) फर्म का पंजीकरण नंबर, GST नंबर सहित प्रस्तुत करना होगा।
- 19) आकर विभाग द्वारा आवंटित फर्म का पैन नंबर जमा किया जाना चाहिए (इसके बिना वेडर की बोली अमान्य हो जाएगी और अस्वीकार करने के लिए उत्तरदायी होगी)।
- 20) यदि किसी स्पष्टीकरण की आवश्यकता है तो उसे बोली जमा करने से पहले ई-मेल pe.rofate@barodeuprrb.co.in पर प्राप्त किया जाना चाहिए।
- 21) बैंक का निर्णय अंतिम होगा और इस संबंध में किसी भी पत्राचार पर विचार नहीं किया जाएगा।
- 22) बोलियां जमा करने/नहीं जमा करने में देरी के मामले में, बैंक कोई जिम्मेदारी नहीं लेगा।
- 23) बैंक बिना कोई कारण बताए किसी भी या सभी निविदाओं को अस्वीकार कर सकता है।
- 24) सामग्री का उपयोग उसी प्रकार और मानक गुणवत्ता का किया जाना चाहिए जैसा कि कोटेशन में उल्लिखित है जिसे आपके द्वारा किसी भी कार्य आदेश के आवंटन के समय/अवधि में स्वीकार किया गया है।
- 25) कार्य पूरा होने के बाद बैंक के पैनल में शामिल आर्किटेक्ट/शाखा प्रबंधक/क्षेत्रीय कार्यालय द्वारा इसका निरीक्षण और सत्यापन किया जाएगा और कोटेशन और संबंधित कार्य आदेश के अनुसार संतुष्टि के बाद ही भुगतान पर विचार किया जाएगा।
- 26) कार्य निष्पादन की अवधि के दौरान वास्तुकार या बैंक का कोई भी अधिकारी स्थल पर कार्यों का निरीक्षण करने के लिए स्वतंत्र होगा। कार्यों की गुणवत्ता में सुधार के लिए परिवर्तन या संशोधन का कोई भी सुझाव नियोजकों और वास्तुकार के सक्षम प्राधिकारी की पूर्व मंजूरी के अधीन किया जाएगा।
- 27) किसी भी विवाद की स्थिति में मामला क्षेत्रीय प्रबंधक, बढ़ीदा यू.पी. बैंक क्षेत्रीय कार्यालय फतेहपुर (उ.प्र.) एवं न्यायिक क्षेत्राधिकार फतेहपुर होगा।

Signature & Seal of the Contractor

Regional Office - SA Gautam Nagar Fatehpur (U.P.) 240110 (0580-211213)
e-mail:rofate@barodeuprrb.co.in



- 28) निविदा में दी गई दरों में केवल जी.एस.टी. शामिल नहीं होगी, लेकिन इसमें सभी उत्पाद कर, चुंगी और अन्य कर शामिल होंगे, किसी भी परिस्थिति में दरों में वृद्धि की अनुमति नहीं दी जाएगी।
- 29) यह निविदा सूचना अनुबंध का हिस्सा बनेगी और उपरोक्त तरीके से निविदा जमा न करने पर आपका प्रस्ताव अस्वीकृति के लिए उत्तरदायी होगा।

फूले बड़ीदा यू.पी. बैंक


क्षेत्रीय प्रबंधक
12

Signature & Seal of the Contractor

Regional Office : CA Goutam Nagar, Fatehpur (U.P.) Tel. : 05180-211213,
e-mail: rofate@barodauprb.co.in



General Information

Name of the vendor.....

Address for correspondence.....

.....

Permanent Address.....

.....

.....

Telephone No/Mobile No.....

.....

PAN NO.....

.....

GST No.....

.....

Email Id.....

Signature & Seal of the Contractor

Regional Office : TA Gachan Nagar Fatahpur (D.P.) Pin : 05160-221213 ,
e-mail:rofat@narodauprct.co.in



Terms & Conditions for Vendors:-

1. Advance is not right of Vendor. The rights of advance to Vendor solely rests with Bank/ organization.
2. Any request of advance from Vendor will only be entertained if work order is of more than Rs. 10.00 Lakhs
3. Only Vendor having valid & active e-mail id should participate in Tender process.
4. Work order sent via e-mail will be considered accepted if there is no response within 3 days of e-mail sent from Regional office.
5. Day to day communication/ instructions will be via e-mail and Vendor should be prompt in replying to every e-mail sent by Regional Office / Architect etc.
6. The tender rate against each item of work / price indicated in the schedule of quantities and rates / price should be indicated both in words and figures. In case of any discrepancy, the rates indicated in words would prevail.
7. The rates quoted against each item of work / price should be for the complete finished item of work and include all labour, material, taxes, overhead, duties, etc. Any statutory change in the tax structure after opening of the tender shall be reimbursed by the Bank as per actual.
8. All tenders in whom any of the prescribed conditions are not fulfilled or incomplete in any respect are liable to be rejected. This tender notice shall form part of the contract documents.

Signature & Seal of the Contractor

Regional Office : 2A Gauranagar Ferozpur (C.P.) Tel: 05180-221213 ;
e-mail: info@ferozpurpcb.com.in



GENERAL CONDITIONS OF CONTRACT

General Instructions to Contractor

Inspection of sites: The contractor shall visit and examine the site and satisfy as to the nature and correct dimensions of work and facilities for obtaining material and shall obtain generally his own information on all matters affecting the execution of work. No extra charge made in consequence of any misunderstanding or incorrect information on any of these points on the ground of insufficient description will be allowed. All expenses incurred by the contractors in connection with obtaining information for submitting this tender including his visit to site and efforts in compiling the tender shall be borne by the tenderer and no claims for reimbursement thereof shall be entertained.

Safety Regulations: The contractor shall take all the necessary precautions while working and to safeguard adjacent property, Bank's property, Bank's employees, and traffic persons.

Compliance to local laws: The contractor shall conform to the provisions of any Act of the Legislature relating to the work and to the Regulation of Bye Laws of any authority. He shall also obtain the permission of the Municipality or any other Authorities if required under the existing rules.

Site cleaning: All the rates quoted are inclusive of removal of rubbish / debris collected during the progress of work, rejected material and clearance of site before and after the work is completed. Not more than one truck load shall be stored that to for not more than 3 days. The contractor shall arrange to remove the same immediately. If the contractor is failing to remove the same and the expenses shall be recovered from the contractor and he will not dispute for the expenses so incurred.

Vouchers / bills: Contractor shall upon the request of the Bank furnish bills, invoices, accounts, receipts and other vouchers for all materials brought on site to prove that the material purchased are as mentioned in the specification.

Contractor's responsibility: The work will from time to time be examined by Project Architect, but such examination shall not in any way exonerate the contractor from the obligation to remedying any defects which may be observed at any stage of the work or after the same is completed.

Dismissal from work: The contractor shall upon the written request of the Project Architect immediately dismiss from the work any person employed by him thereon, who may in the opinion of the authority be incompetent or misconduct himself and such person shall not be again employed on the work, without the permission of the bank.

Order of work, etc.: Bank reserves the right to fix the order in which the various items of work involved are to be executed. However, the contractor shall be responsible for the completion of the entire job within the item limit specified failing which liquidated damages as mentioned in tender clause shall be recovered from the contractor.

Commencement of work: The work must be started within 3rd days upon accepting the work order and the programme for carrying out the various jobs shall be drawn out in consultation with the Project Architect. Adequate labour force shall be provided to complete the work within the specified period. Proper security aspects should be taken care of by adequate vigilance in view of the importance of the

Signature & Seal of the Contractor

Regional Office : 2A Goutam Nagar Fatehpur (U.P.) Tel. : 05180-221213 ;
e-mail: rofate@barodauprb.co.in



building. Default in compliance with the programmes so finalized shall entail operation of liquidated damages as stated.

Subletting the work: The contractor shall not directly or indirectly sublet the work to other party without written permission from the bank.

Quantities of works are provisional: The quantities mentioned in schedule are provisional and likely to increase / decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account

Distribution of work: The Bank reserve the right to distribute the work for which quotation have been called, among more than one parties, if found necessary on common L1 rates. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the bank.

Third party damage: The contractor shall be responsible for all injury to persons, animals, building, building structure, any damage to road, streets, footpaths and shall rectify it at its own cost.

Insurance cover: All the workers of the contractor must be properly covered by an Insurance Policy under Workman's Compensation Act and Fatal Accidents Act. The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract. In case of delay, contractor shall arrange to extend insurance policy till work is completed.

Delay & Extension of time: All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should applying to the Bank explaining, therein the reasons for such delays, immediately and if in the opinion of Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.

Certificate of virtual completion: As soon as the work is completed, the contractor shall inform in writing such completion to the **Project Architect, appointed by bank** who will inspect the work and if satisfied will issue the certificate that the work has been virtually completed and the defects liability period shall commence from the date of such certificate.

Defect liability period: The defects or other faults which may appear during the defect liability period which is 12 months after the virtual completion of the work, arising in the opinion of the bank due to inferior quality of material or bad workmanship not in accordance with the contract, contractor shall make good at his own cost within a reasonable time. In case of default, Bank may employ and pay other agencies to amend and make good such defects and all expenses / damages / losses shall be recoverable by Bank or may be deducted from any money due to the contractor

Arrangement of work: The contractor shall organize the work in such a way that the office users or the nearby public area put to no hardships and the working of the office is not affected. The contractor shall take adequate care during the progress of work to protect the office property like stationery, furniture, etc. In case of any damage, the same shall be made good by the contractor. Contractor is agreed to work after office hours for which no extra cost shall be considered.

Signature & Seal of the Contractor

Regional Office : 2A Deytas Nagar Faridkot (D.P.) (Tel: (01999-20177) ,
e-mail:rodate@narodaupctb.com.in



Stacking of material: The contractor is not to stack any of his material recklessly so as to endanger the safety of the building and cause any nuisance to the occupants and the public.

Extra charges: It must be clearly understood that all the conditions of contracts are intended to be strictly enforced and that no extra charges in respect of extra work will be allowed unless they are clearly outside the spirit and meaning of the condition and unless such work shall have been ordered in writing.

Protection of material and work: The contractor shall be responsible for storing and watching his own material and protecting the work at his own cost. Any damage / spoiling of lift / floor / dado caused during such act will have to be made good by the contractor at his own expenditure.

Water supply: The contractor shall make his own arrangement for water required for the work. In case the water is available and supplied by the Bank, the charges for the same shall be recovered at the rate of 1% of value of the work executed. In case water supplied by the Bank, the contractor shall make his own arrangement for the storage, pipeline from point of take off to the required location.

Electric supply: The contractor shall make his own arrangement for Electricity required for the work or alternative of electricity.

Approval of samples: The contractor shall furnish well in time before work commence at his own cost, color samples, samples of material or workmanship that may be called by Project Architect and bank for approval. Rates quoted shall cover for such preliminary work.

Workmanship: The work involved calls for a high standard of workmanship combined with speed. All the glass panes, door handles / hinges, electric fitting, fans, furniture records, floors etc. are to be thoroughly cleaned after work is completed. Any damage to the flooring, tiles, dado, paneling or any other part of the building, etc. shall be made good at the cost of the contractor to the entire satisfaction of the Bank. Contractor shall make all arrangements for shifting of furniture / records and keeping the same in its original position after he finishes the work on daily basis. The contractor at his own cost shall provide brown paper, polythene, tarpaulin etc. for protecting furniture / fixtures, paneling, electrical, fittings, records, etc.

Interpretation of documents / drawing: Except where otherwise provided in the contract all questions and disputes relating to the meaning of the specifications, design drawings and instructions herein before mentioned and as to the quality of workmanship or materials used for the work or as to any other question, claim, right, matter or thing whatsoever, in any way arising out of or relating to the contract, designs, drawings specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution or failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof shall be referred to the competent authority of the Bank whose decision shall be final and binding on the contractor.

Use of scaffolding: The contractor shall allow the use of scaffolding erected by them to any other agency employed by the Bank during the contract period without any payment.

Provisional Item: If ordered by the Bank, contractor shall be required to carry out provisional items at the same conditions and rates as applicable for this contract.

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05180-221213 ;
e-mail : rofate@barodauprbb.co.in



Measurements of all concealed items: Measurements of all concealed items of work and extra item if any, shall be got recorded by the Project Architect before and bank officials they are checked up.

Measurements: All measurement tapes shall be of steel and all scaffolding and ladders that may be required for taking measurements shall be supplied by the contractor.

Cleaning during the work: The rates quoted shall include cleaning of ceiling roses, electric switches, boards, window panes etc. after the repairing leaving the site neat and tidy from time to time.

Complying I.S. specification: Unless otherwise mentioned in the contract, the latest Indian Standard Code for material specifications, method of work, and mode of measurements shall be followed. The payment shall be made on the basis of actual measurement of work done to be submitted along with bill

Rate to include: The rates quoted by the contractor shall cover for work at any height in the premises for all finished items under this contract. The rate quoted shall be inclusive of all material cost, wastage, labour, loading, profit, taxes if any, scaffolding, transport, supervision, spot light arrangement and any other means to complete the job. Octroi, sales-tax, works contract tax or any other taxes present or future to be included in the rates so quoted.

Price Fluctuation: The rates quoted by the contractor shall be firm throughout the currency of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in the cost of material or labor

The successful tenderer/s if called upon to do so, shall obtain a letter from the approved trade manufacturer whose product is used, if found necessary by the Bank confirming that the manufacturer shall provide all the technical assistance and supervision during the execution of the work at all such places as directed and the contractor shall bear the expenses, if any, for such supervision and technical assistance supplied by the trade manufacturer.

Testing of materials: If at any point of time during the work, if Bank authorities desire to carry out the tests of certain materials, the contractor shall arrange for the same and submit the test report without any extra cost to the Bank.

The contractor shall note that they should bring to the notice of the Architect / Engineer and bank officials any breakage in glass window before starting work. However, if any glass window is found to be broken during the repairing work, the same shall be replaced by the contractor at his own cost.

Conditional tenders: Conditional tenders are liable to be rejected.

Rates of non-tendered items: The successful tenderer is bound to carry out any item of work necessary for the completion of the job even though such items are not included in schedule of quantities.

Abandonment of work: If in any case the work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period.

Signature & Seal of the Contractor

Regional Office P-2A Sector Bagar Katanga, D.D.P./Tel. 26140-00001,
e-mail:rcfat@psnindiauprb.com.in



The Bank reserves the right to accept / reject the lower or any or all tenders in part or in whole without assigning a reason therefor.

Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter cannot be resolved then the same shall be referred to the respected, qualified person in the field agreed to both the parties and his opinion shall be binding on both the parties. However, this is pre course to any legal action in this regard.

Incomplete quotation: Incomplete quotations shall be summarily rejected

Payments: The contractor shall be paid by the Bank from time to time under interim payment on account of works executed and when the value of work equal to the approximate value named in the Appendix as 'Value of work for Interim Certificate' has been executed in accordance with this contract.

When the work has been virtually completed and Bank's Architects / Engineer has certified in writing that the work has been completed on the basis of detailed measurements and has made a final scrutiny and that there is no dispute items, rates, and quantities, the contractor shall be entitled to the payment of the final bill in accordance with the final certificate which will be honoured within the period specified in the Appendix as period of honouring final certificate.

The contractor shall be paid by the Bank within the period named in Appendix (period of honouring certificate) after such certificate has been delivered to the employer (bank) by the Project Architect appointed by bank. Project Architect and bank has power to withhold any certificate in the work or any part thereof are not carried out to his satisfaction or the contractor fails to show the desired progress or fails to follow the instructions given or in case of breach of this contract.

For water proofing works on traces, bathroom, WC, Chajja, work has to be executed through the agency specialized in waterproofing. Contractor will have to submit a guarantee of 10 years on stamp papers as per the format to be prescribed by the Bank.

Retention Money : The retention money built up through retention from interim and final bills will be returned to the contractor after the expiry of defect liability period, subject to deductions for any appropriations thereof required to be made by the Bank as per conditions of the contract. The contractor should note that no interest will be allowed on his security deposit. It will be minimum of 5% of Final verified Bill.

Signature & Seal of the Contractor

Regional Office : BA Gautam Nagar Fatehpur (U.P.) Tel. : 05160-221213,
e-mail:rozofate@parodsuprrb.co.in



The contractor is requested to sign each page of the quotation and put rubber stamp, seal below his signature and seal the quotation in an envelope.

Liquidated damages: If the contractor fails to maintain the required progress or to complete the work and clear the site or before the contract or extended date period of completion, he shall without prejudice to any other right, pay as agreed compensation amount of 1 % of contract amount per week of delay subject to maximum of 10 % of contract amount as liquidated damages.

Records & measurements: Measurements shall be taken jointly by Project Architect and contractor in presence of bank officials and shall without extra charges provide assistance with appliance, labour and other things necessary for the work and measurements will be signed and dated by both the parties on completion of measurements.

Safety measures: The contractor at his own cost shall provide tarpaulins on the external side of the building at the time of breaking plaster etc. to safeguard adjacent property, Bank's property, employees, traffic, etc. The contractor shall follow all the safety measures while carrying out the work. Employer that is Bank shall not be liable for any compensation due to accident, any mishap or negligence.

If there is delay in commencement of work for any reason, the employer that is Bank shall not be liable for any compensation.

If at any point of time during the progress, it is observed that the contractor is not progressing the work with due diligence, care and lagging much behind the schedule or fails to gear up the work despite instructions from Project Architect, the employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case, the contractor shall be liable to pay the employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the Bank will be forfeited.

Although the number of coats of paints / polishing / white washing are specified the contractor will have to additional coats if the surface is not to the satisfaction of the Project Architect & bank and there shall be no extra payment on account of such coats.

First Aid: The contractor shall be responsible for all first aid and he shall keep the site fully equipped to meet such emergency.

Supervision: The contractor is required to have on site during all working hours a competent supervisor (acceptable to Bank) who will be responsible for the conduct of worker and who has authority to receive and act on such instructions issued by the Architect / Engineer of Bank.

All work shall be carried out in a workman-like manner to the entire satisfaction of the Architect / Engineers.

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05180-221213
e-mail:rcotate@barodeaprtb.co.in



Contractor shall follow all rules / regulations in force and should possess the license for employing labour and also follow all safety measures, labour bye law and shall be responsible for any lapse.

Transfer of Tender Documents: Transfer of tender documents purchased by one intending tenderer to another is not permissible.

Safety: The contractor shall carry out the entire work in a workman like manner having full regard for the safety of the men working at site. All safe practices shall be strictly adhered to by the workmen of the contractor like wearing helmets, safety belts when working at heights, gloves when handling sharp objects and reinforcement, eye shields during welding, safety shoes, etc. The contractor shall protect sides of openings in floor slabs, edges of slabs, stairs, stairwells etc. with barricades, warning signs / lights and educate all his workmen regarding following safe working practices. He shall provide first aid boxes at site.

In spite of following safe methods, in case of any unfortunate accident, the contractor shall indemnify the employer against any expenses or claims towards treatment or compensation.

Nuisance: The contractor shall not any time do cause or permit anyone to do or cause any nuisance on the site or do anything which shall cause unnecessary disturbance of inconvenience to the Employer or to the owners, tenants or occupiers of other properties near the site and to the public generally.

Signature & Seal of the Contractor

Regional Office : ZA-Gautam Nagar, Patancheru, V.V.P., Tel.: 06180-231213
e-mail: rrc[at]a@bharatnagarhb.com.in



Rights, remedies and powers:

- l) Termination of contract due to contractor's default. If the contractor:
- a. Abandon the contract.
 - b. At any time defaults in proceedings with the works with due diligence and continues to do so after a notice in writing of seven days from the Engineer or Project Architect or Employer, or
 - c. Commits default in complying with any of the terms and conditions of the contract and does not remedy it within **3RD days** after a notice in writing is given to him in that behalf of the Engineer or Project Architect or Employer.
 - d. Persistently disregards the instructions of the Engineer, Project Architect and bank or contravenes any provision of the contract, or
 - e. Fails to remove materials from the site or to pull down and replace work after receiving from the Engineer, Project Architect notice to the effect that the said materials or works have been rejected.
 - f. Fails to complete the works or items of work on or before the stipulated date (s) of completion, and does not complete them within the period specified in a notice given in writing in that behalf by the Engineer, or Project Architect of Employer, or
 - g. Offer or gives or agrees to give to any person in the Employer's service or to any other person on this behalf, any gift or consideration of any kind as an inducement or reward for doing or forbearing to do so for having done or forbore to do any act in relation to the obtaining or execution of this or any other contract for the Employer, or
 - h. Shall enter into a contract with the Employer in connection with which commission has been paid or agreed to be paid by him or to his knowledge, unless the particulars of any such commission and the terms of payment thereof have previously been disclosed in writing to the Employer / Engineer, or
 - i. Shall obtain a contract with the Employer as a result of ring tendering or other non-bonafide methods of competitive tendency, or
 - j. Being an individual, or if a firm, any partner thereof, shall at any time be adjudged insolvent or have a receiving order or order for administration of his estate made against him or shall take any proceedings for liquidation or composition (other than a voluntary liquidation for the purpose of amalgamation or reconstruction) under any Insolvency Act for the time being in force or make any conveyance or assignment of his effects or composition or arrangement for the benefit of his creditors or support so to do, or any application be made under any Insolvency Act for the time being in force for the sequestration of his estates or if a trust deed be executed by him for benefit of his creditors, or

Signature & Seal of the Contractor

Regional Office : RA Gautam Nagar Fatehpur (U.P.) Tel: +05180-221213 ;
e-mail:rofate@barodauprpb.co.in



- k. Being a company, shall pass a resolution or the court shall make an order for the liquidation of its affairs, or a appointed or circumstances shall arise which entitle the court or debenture holders to appoint a receiver or manager, or
- l. Shall suffer an execution being levied on his goods and allow it to be continued for a period of 21 days, or
- m. Assigns, transfers, sublets (engagement of labour on a piece work basis or of labour with materials not to be incorporated in the work, shall not be deemed to be sub-letting) or attempts to assign, transfer or sub-let the entire works, or any portion thereof without the prior written approval of the employer i.e. bank.
- l) The Bank may, without prejudice to any other right or remedy which shall have accrued or shall accrue thereafter as the Employer by written notice determine the contract either as a whole or in part.
- ii) Rights of the employer after determination of the contract due to contractor's default.

The Engineer shall on such determination have powers to:

- a. Take possession of the site and any materials equipment, plant, implements stores etc. thereon, and / or
- b. Carry out the incomplete work by any means at the risk and cost of the contractor.
- iii) On determination of the contract in full or in part, the Engineer shall determine what amount, if any, is recoverable from the contractor for completion of the works or part of the works or in case the works or part of the works is not to be completed, the loss or damage suffered by the Employer. In determining the amount, credit shall be given to the contractor for the value of the work executed by him upto the time of cancellation or the value of contractor's materials to be present so as to record the measurements in his presence. If the contractor fails to be present in response to the notice, the recording of measurements shall be proceeded with ex-parte and the measurements as recorded shall be binding the contractor.
- iv) The Bank shall have the right to use contractor's plant, machinery and materials on the balance work but shall not in any way be responsible for any damage or loss of the same and the contractor shall not be entitled to any compensation thereof.

Signature & Seal of the Contractor

Regional Office: TA Sautar Nagar Fatehpur (U.P.) (Tel): 401899-201013
e-mail: rcfarc@corodauprrb.co.in



APPENDIX TO THE CONTRACT DOCUMENTS

- Subject:** : Interior Furnishing, Electrical, UPS & Data works for Baroda U. P. Bank at Office/Branch, Distt. FATEHPUR
1. Defect liability period : **12 months** from the date of virtual Completion of work.
2. Date of commencement : **3rd days** after the contract is accepted by The contractor
3. Date of completion : 3 (Three) weeks.
4. Liquidated damages : 1% of contract amount per week / day of delay
Subject to maximum of 10% of contract amount
For the works of less than 6-month completion Period.
5. Period of honouring certificate : **15 days**
6. Retention money : 5% of the bill value will be deducted as retention subject to maximum security deposit. the retention money so held shall be refunded after defects liability period of 12 months of full & final completion of job.
7. Release of Retention money : After 14 days from defect liability period.

Signature & Seal of the Contractor

Regional Office : ZA Gautam Nagar Fatehpur (U.P.) Tel. 185188-221213 ,
e-mail:rofate@barodauprb.co.in



To,

**The Regional Manager,
Baroda U.P. Bank,
Regional Office,
2A Gautam Nagar
IT I Road
Fatehpur-212601**

Dear Sir,

LETTER OF OFFER

Sub: Interior Furnishing, Electrical, UPS & Data & A.C. works for Baroda U P Bank at Office/Branches, Distt. Fatehpur

With reference to the tender regarding the above work invited by you, we have to state as under.

We declare that before quoting the rates, we have visited all the sites and our rates are as per present sites condition. execution of the works at my /our tendered rates as per the Terms of Contract. In the event of this tender being accepted, I / We agree to enter in to and execute the necessary contract documents as required by you.

As required by you, I / We are returning herewith the documents (in single) duly signed by us at each page in token of our acceptance of the provisions in the documents.

We hereby offer to execute and complete the whole of the works strictly in accordance with the said conditions of contract, special conditions of contract, specifications and drawings to be provided by bank at the rates set out against each of the items of work in the schedule of quantities.

We have carefully read and clearly understood the conditions of contracts, special conditions of contract, and specifications. We agree to complete the work at the rate / rates quoted by me / us in the schedule of quantities and within the specified time from the date of work order awarding the work to us.

We understand the work is to be completed within scheduled time period.

Our rates are firm, include and cover all cost, expenses, liabilities of every description and all risk of every kind to be taken in execution and handing over the work to the Bank. The GST, Service Tax, Sales Tax (State & Central), works contract tax, octroi, duties, municipal tax, general tax and any other taxes applicable and prevailing from time to time on such item for which the same are leviable and the rates quoted by us are inclusive of the same.

Thanking You,

Yours faithfully,

Name :
Address :
Mobile No. :

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05180-221213 ,
e-mail:rofate@barodauprrb.co.in



LIST OF FURNISHING MATERIAL

PARTICULARS	Make of Material
Plywood/Block Board	Archid / Century / Green only premium quality. (6mm, 9mm, 12mm, 19mm)
Laminates	Greenlam / Century / Archid . (1.0mm thick) as per bank approved color
Soft Board (Pin up Board)	Jolly Board, Stylex
Gyp Board	India Gypsum/Armstrong/Gyproc
Metal Ceiling	Armstrong
Vertical Blinds	Vista, Universal, Maac
Screws	GKW / Mettie fold , Hindalco
SS Hinges	Godrej / Hardwyn
Hardware	Hardwyn, Godrej
Drawer shutter lock	Godrej , Link, Dorset
Ball catch	Hardwyn, Godrej
Door lock / Handles	Hardwyn, Godrej
Veneer	Archid / Century / Green
Adhesives	Fevicol, Mahacol, Jeeevanjor
Wood Preservatives	Black Japan ..
Door closure	Hardwyn, Godrej
Glass	Modi / Asahi / Saint Gobain
Glass tinted	Same as above.
Melamine Polish	Asian Paint, Nerolac . French . Zinc oxide .
Paint	Burger, Nerolac, Asain
Vitrified tiles	Marbonite Jhonson, Kajaria
Ceramic Tiles	Jhonson & Jhonson, Kajaria,
Alu. Door & Window Sections	Jindal / Bhansail .
Floor springs	Hardwyn, Godrej
Rubber foam	34 density mm foam

NOTE: All materials shall confirm to IS / BIS respective numbers.

- Commercial ply shall conform to IS 303.
- Marine Ply shall conform to IS 710
- Block Board shall conform to IS 1659.

Signature & Seal of the Contractor

Regional Office : ZA Gautam Nagar Fatehpur (U.P.)Tel. :05140-221213 ;
e-mail:rofate@baredauprb.co.in



LIST OF APPROVED MANUFACTURERS / SUPPLIERS OF MATERIALS

MATERIALS	APPROVED MANUFACTURERS /SUPPLIERS
S & F / Light fixtures / Patti	Philips / Wipro
1x 18 w LED	Philips /Wipro
Switch, sockets, conceal box, plate/ Change over switch	Philips/ Orient
MCCB	L&T / Siemens
Bus bar / TPN LDB, TPN MCB / DP MCB / SPN UPDB / MCB & DB/ELCB/RCCB	Siemens / L&T
LT Cable / Telephone cable	Delton / Polycab
Light / circuit wiring / Cable ISI / PVC insulated wire ISI	Havells/ Polycab / Finolex / R.R. Kable / L&T
Floor conduits MMS Grade / PVC conduits & accessories	Precision / Wimco / X-press
Music cum Public address system	Bosch / Sony
Low Fourteension switch fuse unit with HRC fuse	L&T, Siemens
Timer	Lea grand
Gland Flang type	Braco
Lugs / Wooden screw	Dorma, Hardwyn, Godrej
Telephone tag block	Krone Box
Wall / Ceiling / Exhaust fans	Crompton / Usha /Orient
CAT – 6 Cable / CAT-6 I/O	D-link / DiGi link

Signature & Seal of the Contractor

Regional Office :- DA Gautam Nagar Fatehpur (U.P.) Tel :- 05140-221017 ;
e-mail: info@fatehbarodasprbh.co.in



PREAMBLE TO BOQ

Abbreviations:

R.M.T	:	Running Meter
Sq. Mt.	:	Square Meter
Sq. Ft.	:	Square Foot
Cu. Mt.	:	Cubic Meter
T.W.	:	Teak Wood
Q.R.O.	:	Quote Rate Only
C / C	:	Centre to Centre
M.T	:	Metric Ton
C.P.	:	Chrome Plated
NO.	:	Numbers
MM	:	Millimeter

1. All dimensions are in M.K.S. unless otherwise stated.
2. The quoted rate shall be all inclusive and cover the cost of material including wastage, freight, all types of taxes, duties, royalties, erection, construction, testing of materials if required samples brought for approval, tools and tacks, plant and equipments, supervision, overheads, profit and any other expenditure incurred for completion of work as per drawings, specifications and to the full satisfaction of BANK / Architect.
3. The rates quoted shall be valid for working at all heights, depths and on all floor levels. No extra payment shall be made for scaffolding, staging, ladders etc for transportation of men and materials at higher or lower levels.
4. The item rate specifications are indicative. the contractor will have to carry out the work in accordance with the drawings, technical specifications and / or other conditions laid down in tender document and to the full satisfaction of BANK / Architect.
5. Quantities mentioned against respective items are approximate and can vary to any extent. Payment shall be made on actually executed quantities.
6. No claims shall be entertained in case of increase / decrease quantities of any item and also to add / delete any item in totality. BANK / Architect reserve the right of operating any item for any work.
7. Rates for painting shall include cleaning glass panels, floors etc.
8. After completion of work the site shall be handed over absolutely clean, after ensuring that all floors, walls etc. are spotlessly clean.
9. Rates of all items shall remain constant irrespective of floor level and no extra shall be paid for handling and stacking of materials, removing debris etc. from the site.
10. Unless otherwise noted, the method of measurement will be as per I.S. 1200.
11. BANK / Architect reserve the right of operating all ' Quote Rate only ' items.

Signature & Seal of the Contractor

Regional Office : 2A Seetan Nagar Patancheru (D.P.) T.N.L. : 05189-271212 ;
e-mail: rnfate@narcdkumrbh.co.in



12. Wherever contractor proposes to use 'equivalent' makes (i.e. other than specified) he shall obtain BANK's prior approval. BANK may ask Architect before giving approval to the same. Any additional cost and time lost due to this will be on Contractor's account and no claims will be entertained.
13. The rate of partition, panelling shall include necessary additional framework supports that may be required to suit site conditions or stability of the item. Decision of Architect in regards to the need for such additional supports shall be final.
14. All wooden frame work/ member size mentioned as out of, shall be full size with maximum planning tolerance of 3 mm both ways.
15. Rates for doors include all brass oxidized heavy duty hardware, locks, floor springs, door springs, door closer, special door handles etc as specified in relative terms.
16. Size and type of door closer/ floor spring shall be suitable for type of door. The contractor shall give guarantee for performance of door closer / floor spring from manufacturer.
17. Rates for partitions, panelling shall include making of necessary cut outs, chasing to be made for conduits, switch boards etc.
18. Rates for painting and polishing shall include cleaning glass panels, fans floor etc.
19. After completion of work the site shall be handed over absolutely clean, after ensuring that all laminates, floors wall etc are spotlessly clean
20. Contractor shall clean the site and mark the lining out on the floor with adhesive tape for approval. The same shall not be paid separately.
21. In case of loose furniture, the specification for side unit or rear side credenza unit in any item shall be same as the specification of the table in that item.
22. All key hoes should be fixed with metallic key hole ring.
23. Key for all locks should be different and no key should match with two different locks.
24. Rates shall include for following: -

PLASTERING:

- a) Work at all levels, heights and in all situations and profiles.
- b) Double scaffolding, working platforms / Tarpaulin curtains.
- c) Coving, drip moulds, grooves, recesses, ornamental bands etc.
- d) A coat of white wash for neeru plaster soon after curing period is over.
- e) Work in narrow width and small quantities unless special provision is made to the contrary.
- f) Preparation of surface by ranking out joints in brick or by hacking the concrete surface and wetting the surface before plastering wherever required.
- g) Thickness of plaster exclusive of the thickness of key i.e. grooves and open joints in brick work, stone work etc.
- h) Chambers of any width, internal and external rounded angle
- i) Curling, protection and cleaning of all surfaces.
- j) Keeping all plastered surfaces well wetted for at least 7 days.

PAINTING & POLISHING:

- a) Works at all heights and use of all scaffolding, necessary for execution of work and for inspection.
- b) Preparing surfaces to receive finishing coats.
- c) Putting sand papering and dusting of surface in between coats where applicable.
- d) Work on cornices, narrow bands and widths, grooves etc.
- e) Finishing to approved matt textures, complete as directed.
- f) Spreading and removing, covering to doors, windows, floors, fittings etc to protect them from splashes.
- g) Washing floors, cleaning glass, joinery, electric fittings etc and leaving premises clean and tidy.
- h) Mode of Measurement

Sr.No	Particulars	Method of Measurement	Multiplying Factors
1	Panelled doors & Windows		1.125 for each side
2	Fully glazed		0.5 for each side

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05190-221213 ,
e-mail: rofate@barodakuprrb.co.in



3	Partly glazed & panelled	Measured flat not girthed including frame	1.0 for each side
4	Flush door		1.0 for each side
5	M.S.Grill & Collapsible door		1.0 for painting all over.
6	Rolling Shutter	Measured flat not girthed including frame	1.25 for each side

Mode of Measurements:

- 1 Partition, Panelling : Sq. Ft. Area - one side only
- 2 Painting : Sq. Ft. Finished area only
- 3 Rounding off Measurements : All measurements shall be rounded off to nearest 2 decimal points.

Signature & Seal of the Contractor

Regional Office : CA Section, Nagar, Faridkot, Distt. Feroz, 151005-0000117
 e-mail:cafar@caafaridkot.gov.in



ANNXURE-I**Summary****BARODA U. P. BANK****Office / BRANCH DISTT- FATEHPUR**

Sr. No.	Description	Section	Amount of Tender
1.	Furnishing works	in digits	
		in words	
2.	Electrical & Data Cabling works	in Digits	
		In words	
	TOTAL	in Digits	
		In words	

(GST Extra as applicable)

Note :-

1. All materials to be used strictly follow the list of approved materials.
2. Any deviation in the use of materials at site other than approved materials list will not be permitted and the bank may cancel the contract at any time for any such misconduct & colour as per bran manual.
3. The workman ship and quality of work should be of good quality and to be satisfaction level of the bank's architect and bank

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05180-221212 ,
e-mail:rofate@barodauprb.co.in



**TENDER OF FURNISHING WORKS FOR BARODA U. P. BANK SITUATED AT OFFICES/BRANCHES,
DISTT. FATEHPUR**

1. FURNISHING WORKS:-

S.No.	ITEMS	QTY	UNIT	RATE	AMOUNT
1	FALSE CEILING: - (Gyp board)				
	Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5 mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work.	1.0	SQFT		
1.A	24" x 24" Grid False Ceiling (FINE FISSURED PLANKS): Providing and Fixing False ceiling Grid using hot dipped Galvanized steel sections, exposed surface chemically cleaned capping pre-finished baked polyester paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x 24mm at 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x 600mm. The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/23 of 1987, Noise reduction co-eff. (NRC) of 0.50, Ligh	1.0	SQFT		
2.	PARTITION				
	Providing and fixing partition in position as per design with 2' x 1.5" Aluminum section finished frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil. The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be				

Signature & Seal of the Contractor

Regional Office : 2A Daurah Nagar Fatehpur (O.P.) Distt. 153105-010011,
e-mail:tofo@barodapcb.co.in



	cladded with 10mm thick comm. Ply both sides and to be finished with approved 1 mm laminate (color with vertical grain) as per design with adhesive. 3' high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 8 to 10mm thick. Glass with etching and bank logo.				
A	PARTLY GLAZED PARTITION				
I	PARTLY GLAZED CASH CABIN PARTITION UPTO 7'-0" HT.	1.00	SQFT		
II	PARTLY GLAZED MANAGER CABIN PARTITION UPTO 4'-6" HT.	1.00	SQFT		
III	PARTLY GLAZED LOW HEIGHT PARTITION UPTO 4'-0" HT.	1.00	SQFT		
IV	Front Glass in Low Height Counters	1.00	SQFT		
B	BLOCKED PARTITION				
I	BLOCKED PARTITION UPTO 5'-0" HEIGHT REAR PARTITION:-	1.0	SQFT		
3	DOORS				
	Providing and fixing solid core 38mm solid core flush door finished with lippings in all side with necessary door hinges, cylindrical locks (golden, Godrej), door clouser, door stoppers, etc with a frame work of T.W./ Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished, edges to be finished with wooden lippings. A wooden molding size 1.5" x 2/8" to be provided all along the periferi of the frame work in the both sides. All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8mm thk etched or plain glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary moldings.				
I	Flap Door	1.00	SQFT		
II	FULLY GLAZED ENT. DOOR WITH ALUMINIUM PARTITION				
	P/F toughened glass (12mm thk.) door with pencil polish edges all around and including glass film of pattern and emblem as per design fixed with necessary patch fittings assembly including top and bottom patches, heavy duty floor Machine, bottom lock, SS brushed finished 2' long and 1" dia. handle	1.00	SQFT		

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel: +05140-221213 ,
e-mail:rofate@barodauprrcb.co.in



	on both sides of shutter etc. all complete as directed by Bank.				
4.	CASH COUNTER:-				
	For customer as per layout with provision of 3'-9" high, 2'-6" deep with shelf for CPU and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces with key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.	1'-0"	RFT.		
5.	OFFICER COUNTER				
I	For customer as per layout with provision of 2'-6" high, 2'-6" deep with shelf for CPU and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces. With key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.	1'-0"	RFT		
II	Manager Table:- 6' x 3' H = 2'-6" Providing and fixing MANEGER'S TABLE 6'-0"x3'-0"x2'-6" (ht.) and 10mm beveled glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing . made up of 19 mm commercial board of approved make the finished with 1 mm thick laminate of approved make and shad as approved as par detailed drawing. Table shall be provided with 3 drawers sliding on telescopic channels with proper locking arrangements and keyboard with telescope channels tabletop shall be finished with 1.0 mm thick laminate of approved shade & quality . The work includes provided and fixing locks , wire manager , spirit polishing of steam beach bending etc. complete in all respects to the entire satisfaction of the architect.	1 nos.	EACH		
III	Officer Table:- 4'-0"x 2'-6" H = 2'-6" *Same Specification as above	1 nos.	EACH		
6.	STORAGE				
	Providing and fixing Full height storage 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (colour, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block				

Signature & Seal of the Contractor

Regional Office - JA Gauran Nagar Fatehpur (U.P.) Tel: 105190-121211,
 e-mail: rofate@barodauprtd.co.in



	board and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / mouldings duly polished all complete.				
I	Low Height storage (2'-6" ht).	1.00	SQFT		
II	Full height storage (7'-0" ht).	1.00	SQFT		
7.	CHEQUE DEPOSIT BOX (450x300x700)				
	Providing and making cheque drop box 1.5'x1'x9" deep as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardware and locking and side opening arrangements.	1 NOS.	EACH		
8.	SUGGESTION BOX (450x300x700)				
	Providing and making Suggestion box 1.5'x1'x9" deep as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardware and locking and side opening arrangements.	1 NOS.	EACH		
9.	WALL MOUNTED WRITING TABLE (1'-3" TO 1'-6" WIDE AND LENGTH 5'-0")				
	Providing and Fixing wall mounted writing tables as per design. The base of the table shall be a frame of wooden members mounted on a wooden base. The top shall be of 1" comm. Ply finished in 1.5 mm laminate the edge of the top shall be provided with a wooden moulding ¾" x 3" finished in melamine.	1 NOS.	EACH		
10	NOTICE BOARD (1200x900)	1 NOS.	EACH		
	Providing & fixing Notice Board the tag board of approved make & design, of size 4' X 3', with anodized aluminium boarder/frame type. The board should be 3/4" th. Straw board with velvet type fabric lining of appr'd. Colour.				
11.	METER BOX	1.00	SQFT		
	Providing and fixing Meter Box 400mm deep				

Signature & Seal of the Contractor

Regional Office : 2A, Gaurav Nagar, Patancheru, H.P., T.S. 500075
 e-mail: rnfat@narndaprrb.com



	made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front clad with 1.0mm laminate (colour, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / mouldings duly polished all complete.				
12.	WALL PANELLING Providing and fixing panelling on wall. Framing shall consist of Aluminium Section 1"X1.5" (Wall Thickness 2 mm) @ 2'0" C/C. Both ways horizontally and vertically on the wall. This framing would be covered by ½" thick. Ply and 10mm thick gypsum board.				
I	Banking Hall 4'-0" height	1.00	SQFT		
II	Manager cabin 4'-6" Height	1.00	SQFT		
III	Cash Cabin Panelling	1.00	SQFT		
IV	Column Panelling	1.00	SQFT		
TOTAL OF FURNISHING WORKS				Rs.	

(*GST Extra as applicable)

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05100-221313 ;
e-mail: rofate@barodauprrb.co.in



2. ELECTRICAL & DATA CABLEING WORKS:-

S.No.	ITEMS	QTY	UNIT	RATE	AMOUNT
1	<p>Wiring for light points, fan points, bell points, sockets etc.</p> <p>with 1.5 Sq.mm PVC insulated, 1100 V grade grade copper conductor wires and 1.0 Sq mm copper earth wire and 1.0 Sq mm copper earth wire in concealed/surface using PVC (Heavy)25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where where ever required) and chromium plated brass screws/rowel plugs etc.. The conduits to be laid in ceiling with proper clamps/wall/floor and filling the chase with cement mortar and finish the same in original form/wooden partition/above false ceiling with proper clamps (wherever required as per standard specification.</p>				
	<p>NOTE:</p> <p>a) Each circuit shall have independent earth wire.</p> <p>b) Each point shall be earthed.</p>				
I	One light point controlled by one 6A modular one way switch.	1 nos.	EACH		
II	A set of two light points controlled by one 6A modular one way switch.	1 nos.	EACH		
III	One wall fan point with 6A 3 pin socket controlled by one 6A modular one way switch. The switch should be at switch board level.	1 Nos.	EACH		
IV	One Ceiling fan point with 6A 3 pin socket controlled by one 6A modular one way switch. The switch should be at switch board level.	1 Nos.	EACH		
V	One exhaust fan point with ceiling rose controlled by one 6A modular one way switch.	1 nos.	EACH		
VI	One call bell point with ceiling rose/6A 3Pin socket controlled by one 6A modular bell push switch.	1 nos.	EACH		
VII	One 6A 5Pin socket controlled by 6A modular one way switch				
a	Dependent	1 Nos.	EACH		
b	Independent	1 nos.	EACH		
	[FOR ITEM NO. 'I' TO 'VII' ALL MOUNTING BOXES, INNER PLATES, MODULES, COVER PLATES ETC. SHALL BE CRABTREE MEGA SERIES, PLATINUM RANGE MATERIAL (OR EQUIVALENT OF ABB/M.K.) ONLY]				
2.	<p>CIRCUIT WIRING:</p> <p>circuit wiring starting from DB to point control box/switch box using PVC (Heavy)</p>	1.00	RMT		

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Patanchpur (B.P.)Del. 110019-222113;
e-mail:safate@facode.mprb.cu.in



	25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where ever required) with 2x2.5 sqmm PVC insulated 1100V grade multi-stranded copper conductor wire and 1.5 sqmm PVC insulated earth wire and 1.5sqmm. PVC insulated earth Wire (colour code to be used). Identification ferrules at both end to be provided. (Flexible conduit/elbow NOT allowed)				
3.	POWER POINTS				
	Same as serial no. 1, but wiring for 16A 6-Pin socket by using 4 sq mm PVC insulated 1100V grade copper conductor wire with independent 2.5 sqmm earth wire from D.B. to first 1st. Socket and 1st socket to 2nd Socket with 2.5 sqmm and 1.5 sqmm earth wire including providing and fixing of 16A 6-Pin socket with 16A switch				
I	Power point with 4sqmm copper	1.00	EACH		
II	Power point with 2.5sqmm copper conductor wires.	1.00	EACH		
	FOR ITEM NO. "I" & "II" SHALL BE CRABTREE (OR EQUIVALENT OF ABB/M.K.) MAKE MODULAR/DOUBLE MODULE WITH ALL ACCESSORIES ONLY				
4.	A.C. POINTS:				
	A.C. points i/c Box, MCB, Socket, Switch i/c 32 C MCB complete	1.00	NOS.		
5.	DISTRIBUTION BOARDS:				
	Supplying, installation, testing and commissioning of DOUBLE DOOR type distribution boards ORIGINAL FACTORY FABRICATED ONLY) of following specifications:				
I	4-WAY TPN DB (POWER & AC DB)				
	INCOMER :63A 4P OUTGOING: 32A SP MCB-6Nos. 25A SP MCB-6 Nos. (FOR SPLIT/WINDOW A.C. & POWER POINTS)	1 NOS.	EACH		
II	4-WAY TPN DB (LIGHT & FAN DB)				
	INCOMER :40A 4P, MCB-1No. OUTGOING: 10A SP MCB-12Nos.	1 NOS.	EACH		
III	Supplying & Fixing of 1 no. 40A DP MCB in 4 way SPN DB (FOR UPS OUT-PUT AT S/R)	1 NOS.	EACH		
IV	8-way SPN DB with 32A ELCB+D.P. 100mA sensitivity Controlling 6 nos. 10Amp. SP MCB and blanking plates. (FOR UPS OUT-PUT AT HALL)	1 NOS.	EACH		

Signature & Seal of the Contractor

Regional Office : 2A Gautam Nagar Fatehpur (U.P.) Tel. : 05188-221213 ;
e-mail: rcofate@barodasuprrb.co.in



6.	MAIN PANEL			
	<p>Designing, manufacturing, installation, testing and commissioning of cubical type MAIN PANEL made from 16 SWG CRCA sheet steel, T type base M.S. Channel for grouting on floor complete with MCCBs, MCBs, Meters, C.T. etc. complete in all respect, insulated bus-bar with heat shrinkable PVC sleeve in suitable bus-bar chamber, wiring, name plates, danger plate, earth-bus etc. & comprising of compartments with hinged doors and rubber gasket, bus-bar chamber with bolted door and rubber gasket etc. The panel being of dust & vermin proof construction and to be painted with primer and smoke grey paint (minimum two coats) to look attractive. The panel should be comprising with the followings: Degree of Protection IP-54)</p> <p>INCOMER:</p> <p>100A HRC fuse base and bridge with HRC fuses Natural link for three phase four wire system- 1Set</p> <p>100A, 25KA, 4P MCCB ----1 NO.</p> <p>100A 4-P, ON LOAD change over switch-1NO.</p> <p>160A capacity aluminium bus-bar with heat shrinkable proper insulation with colour coated.</p> <p>Digital ammeter and voltmeter with selector switches.</p> <p>R-Y-B phase indicators with 2A backup HRC fuse.</p> <p>OUTGOING:</p> <p>63A 4-P MCCB, 25KA, -3Nos.</p> <p>63A 4-P ON LOAD change over switch (FOR SYSTEM ROOM/ATM) - 1No.</p> <p>40A 4-P MCCB, 25KA - 1 No.</p> <p>32A TPN MCB, 25KA - 1No.</p>	1 NOS.	EACH	
7.	Supplying, installation, testing and commissioning of following light fixtures, fans etc.			
A	PHILIPS/WIPRO/C.G./HAVELLS Make light fixtures			
I	S/F of LED 2X2 Light fixture instead of equal Luminous LED light of Philips by the name of Green Square Led Luminaries on	1 NOS.	EACH	
II	S/F of down light LED Luminaries with reflector (Havel's/Crompton/Philips)	1 NOS.	EACH	

Signature & Seal of the Contractor

Regional Office : 2A Gaurah Nagar Fatehpur (U.P.) Tel. : 05180-221213 ,
e-mail:rofatc@barod@upcrb.co.in



	complete with cutting of false ceiling 15 watt LED.				
III	LED Strip Light (Cove Light)	1.0	RFT		
IV	S/F of LED 4' wide (Patti) Light fixtures	1 NOS.	EACH		
V	S/F of LED 2' wide (Patti) Light fixtures	1 NOS.	EACH		
VI	Supply & fixing of 4' wide double tube set with 2' length Hanging iron rod and Box in Banking Hall complete with necessary fixture	1 SET	NOS EACH		
B	CROMPTON GREAVES make fans				
I	400mm SDX120 Wall Mounted fan.	1 NOS.	EACH		
II	Ceiling fan	1 NOS.	EACH		
C	CROMPTON/GE-ALOSTHOM make				
I	18" Exhaust fans Commercial/ industrial with clamps, bolt/dash fastener by grouting on wall for Banking Hall.	1 NOS.	EACH		
II	12" Exhaust fans with clamps, bolt/dash fastener by grouting on wall for Toilets.	1 NOS.	EACH		
8.	COMPUTER POINT				
I	Wiring with 6x2.5 sqmm + 1x1/5 sq mm PVC insulated 1100 V grade multi stranded copper conductor wires in 2 mm thick PVC conduit from UPSDB to computer point. Each point to have 3 nos 6A -5 Pin modular type sockets, one 6A indicator at below the top of table/counter and controlled by one 16A modular switch at above the table top in wooden partition with all accessories, inner/outer plates, metal box etc. and to be fixed on wooden partitions/by grouting on wall etc. as per the requirement at site.	1 NOS.	EACH		
II	Supply & fixing of porcelain fuse 63 Amp with neutral	1 NOS.	EACH		
III	Cut out 63 AP	1 NOS.	EACH		
IV	UPS wiring for UPS	1.00	MTR		
9.	TELEPHONE POINT / DATA CABEL				
a.	Providing/Laying of Cat 6 Cable	1.00	MTR		
b.	Patch Cord 2 Meter	1 NOS.	EACH		
c.	Patch Cord 1Meter	1 NOS.	EACH		
d.	I/O box	1 NOS.	EACH		
e.	RJ 45 Connector	1 NOS.	EACH		
f.	Tray	1 NOS.	EACH		
g.	Cable Manager	1 NOS.	EACH		
h.	9 U Rack (Note:-All products should be D-Link, TP Link or equivalent International Quality.)	1 NOS.	EACH		

Signature & Seal of the Contractor

Regional Office | ZA Gautam Nagar, Fatehpur (U.P.) Tel. 105180-221213,
e-mail:rofare@barndsuprrb.co.in



10.	Telephone Wiring S/F of 1x8-port switch for telephone wiring connections.	1 NOS.	EACH		
11	Earthing				
A	Providing and fixing of following earth station as per IS:3043, with water pouring pipes, GI funnels, masonry brick chamber with CI cover, including excavation & refilling of pit after filling with charcoal, salt and sand, identification of pit as required.				
I	600x600x3.15mm Copper Plate Earth Station.	1 NOS.	EACH		
II	50mm dia (16SWG & 7mtr. Length) GI Pipe Earth Station.	1 NOS.	EACH		
B	Supplying, Laying and terminating of the following tapes/wires with suitable G.I./copper clamps.				
I	25x3mm Copper strip with copper clamps.	1.00	RMT		
II	1x8SWG Copper earth wire in PVC conduit inside the Branch.	1.00	RMT		
12.	CIRCUIT WIRING FOR POWER SOCKETS & A.C. WIRING				
I	10 mm FR PVC Copper wire & 2.5 mm insulated copper earth wire in 25 mm dia. 2 mm thick PVC conduit ISI mark.	1.00	RMT		
II	2.5 mm & 1.5 mm insulated copper earth wire in 25 mm dia. 2 mm thick PVC conduit ISI mark.	1.00	RMT		
III	4 x 16 mm + 2 x 6 mm pvc wiring in 25 mm dia conduit for main line.	1.00	RMT		
IV	4x4 mm + 1 x 2.5 mm pvc wiring/UPS to MCB in 20 mm dia conduit for pipe.	1.00	RMT		
TOTAL ELECTRICAL & DATA CABELING WORKS				Rs.	

(*GST Extra as applicable)

Signature & Seal of the Contractor

Regional Office : ZA Gautam Nagar Fatehpur (U.P.) Tel. 105190-321213 ,
e-mail: rofats@barodauprrb.co.in

