



बड़ौदा यू.पी. बैंक
Baroda U.P. Bank

RO/KAND/05/P&E/2024-25/251

Date 06-03-2025

SHORT TERM TENDER NOTICE
(For Empanelled Furnishers & Interior Decorators only)

INTERIOR DECORATION WORK IN MUNGISAPUR
BRANCH OF BARODA U.P. BANK

IMPORTANT DATES

DATE OF ISSUE OF TENDER NOTICE	06-03-2025
LAST DATE AND TIME OF SUBMISSION OF TENDER	27-03-2025 up to 05:00 P.M.
DATE OF OPENING OF TENDER (FINANCIAL BID)	28-03-2025 at 03:00 P.M.

Baroda U.P. Bank
Regional office Kanpur Dehat
Nabipur, Jainpur Kanpur Dehat
209311(U.P.)


Senior Manager

Date: 06-03-2025



NOTICE INVITING TENDER

Sealed item rate short-term tenders are being requested on behalf of the Regional Manager of Baroda U.P. Bank. We are seeking proposals from Furnishers and Interior Decorators who are currently empaneled with Baroda U.P. Bank for the interior decoration work at the Mungisapur Branch of Baroda U.P. Bank, located at the Regional Office in Kanpur Dehat. Interested parties are encouraged to submit their bids for consideration.

- **Issue of tender documents** 06/03/2025
 - **Last date of receipt of tender documents** 27/03/2025 up to 5.00 PM
 - **Date of opening of tender documents** 28/03/2025 at 03.00 PM
 - **Place of submission & opening of tender** Baroda U.P. Bank, Regional Office, Kanpur Dehat
 - **Period for completion of work from order date** Maximum 30 days
 - **Retention percentage** 10% (Ten percent) from final bill
 - **Defect liability period** 12 months from the date of completion certificate issued by the Bank Architect.
 - **Release of retention money** After 14 days from defect liability period
- Tenders must be submitted in a sealed envelope clearly labeled as **"Tender for Furnishing & Interior Decoration Work in Mungisapur Branch of Baroda U.P. Bank, Regional Office, Kanpur Dehat."**
- Bids must be submitted in person or by Registered Post.
- The bid must contain two envelopes, as outlined in the procedure below:
- The first envelope must contain all of the documents listed below:
 1. A photocopy of your PAN Number, duly attested.
 2. A photocopy of your GST Number, duly attested.
 3. Registration Certificates for both types of work 'furniture & fixture work' and 'Electric & data cabling work'.
 4. All documents must be self-attested and stamped by the Firm.
 5. It is essential to clearly mention **"DOCUMENTS SUBMITTED FOR BID OF FURNISHING & INTERIOR DECORATION WORK IN MUNGISAPUR BRANCH"** on the envelope.
 - The Second envelope must contain all of the documents listed below:
 1. The second envelope should only contain the price bid and nothing else.
 2. The price must be submitted in the prescribed format provided.
 3. Price bids will not be accepted on any other format or document.
 4. It is essential to clearly mention **"PRICE BID OF FURNISHING & INTERIOR DECORATION WORK IN MUNGISAPUR BRANCH"** on the envelope.
- Both envelopes must be placed in a third sealed envelope and labeled with **"BID FURNISHING & INTERIOR DECORATION WORK IN MUNGISAPUR BRANCH."**



GENERAL INSTRUCTIONS FOR TENDERERS

- Work Completion Time: One Month (From the date of work order)
- The work outlined in this tender must be carried out and completed within one month in accordance with the Tender Document, Bill of Quantities, Drawings, and Instructions to the satisfaction of the Architects and the Bank. A penalty of 1% per day of the total work awarded will be imposed for any delays in completion.
- The term "**Contractor**" refers to the successful tenderer who will be awarded the Contract.
- Contractors must provide rates in both figures and words. Any corrections or overwriting should be initialed by the Contractor.
- Tenders must be submitted by the Contractor with a seal, signature, and date on each page.
- Contractors must submit the costs of the main items as per tender specifications. Any modifications after the contract has been awarded will not be allowed unless there are specific instructions from the Bank/Architect to change specifications.
- The contract is time-bound, and the work must be completed within the specified time limit in the tender notice. This is a working office, and the contractor must ensure minimal disruption to regular services.
- The decision of the Employer and the Architect is final and binding.
- The contractor must submit a registration certificate for both "furniture & fixture work" and "Electric & data cabling work" in separate envelopes labeled "Technical Bid for furnishing & electrical work."
- The contractor must submit tenders for both "furniture & fixture work" and "Electric & data cabling work." Partially completed tenders will be rejected.
- The contractor is responsible for installing electrical fixtures and light points according to the drawings provided. Wires must be drawn from the existing positions of light points and power points, as necessary.
- The contractor must also provide a certificate from an electrical contractor who holds the necessary license/certification from the Directorate of Electrical Safety (U.P.) or a competent authority in another state.



TERMS & CONDITIONS

- Unless stated otherwise, all works are not subject to any allowance for waste. The price for all items will include all necessary straight and curved edges unless otherwise specified or measured separately.
- Any damage to the work before the site is handed over must be replaced or repaired at the contractor's expense to the satisfaction of the Architect/Bank.
- Income Tax and other applicable taxes will be deducted at the source in accordance with the Income Tax Act/Rules.
- The quantities listed are subject to change. Payment for the bill will be based on the actual measurements certified by the architect, not exceeding the total value quoted in the tender form.
- The Architect or any officer of the Employers will have the freedom to inspect the work at the site during the execution period. Any suggestions for changes or modifications to enhance the quality of work will be implemented only after receiving approval from the competent authority of the employers and the Architect.
- Failure to commence work after accepting the work order, leaving work incomplete, not rectifying defective work, or violating the terms and conditions will result in the contractor being de-panelled or blacklisted.
- For any work not included in the contract or any unforeseen work, payment will be made based on approved rates for similar work, as determined by the Architect following the current PWD schedule of rates or analysis of material costs, labor rates, and a 10% profit margin for the Contractor. The Contractor must obtain written approval before undertaking any additional work.
- The bidders must sign each page of the tender documents, including the attached drawings.
- The amount should be provided in both numerical figures and written words. If there is a discrepancy between the rates in words and figures, the written amount will be considered final.
- The Contractor is responsible for arranging and covering the cost of storing materials, plants, and tools. The Employer will not be responsible for the security of the Contractor's materials. No tools or plants will be provided by the bank.
- The Employer/Architect reserves the right to accept or reject any tender without explanation, and their decision will be final.
- If the Contractor breaches the contract by making slow progress or causing damage, the Employer or Architect may terminate the contract without further explanation.
- The Architect is authorized to request the contractor to provide samples, colors, or test certificates from any government or authorized agent for any materials used or to be used in the project. The contractor will be responsible for covering the expenses associated with this.



- The Employer will not be held liable for any damages or compensation resulting from accidents or injuries to any workers or individuals employed by the Contractor or any subcontractors.
- Upon completion of the project, the contractor is required to remove all debris, rubbish, materials, tools, and laborers from the site within three days. Failure to do so may result in the Employer disposing of the materials at the contractor's expense.
- Any disputes will be resolved by the Regional Manager of Baroda U.P. Bank at the Regional Office in Kanpur Dehat, Uttar Pradesh.
- Final payment for the project will be made upon completion, with the Architect certifying the work and deducting retention money as necessary.
- The rates provided in the tender do not include GST but cover all excise taxes. There will be no allowance for rate escalation under any circumstances.



Estimate for Furnishing works for Baroda U.P. Bank

Branch at Mugisapur

Region - Kanpur Dehat

- 1.No offsite prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect.
 - 2.No payment shall be made for any in completed or unsatisfactory work.
 - 3.The Contractor should strictly follow the Booklet requirements of the Bank.
 - including the detailed drawings in the booklet. Any discrepancy between the booklet and the Specifications below should be brought to the notice of the Architect.
 4. List of material to be strictly as per the booklet.
 5. Cable Managers to be provided in the tables and Counters wherever required.
 6. All underframe should be properly treated with antitermite and waterproofing material.
 7. All Locks in the drawers and doorsetc.should be of Godrej.
 8. All keyboard Trays and Drawers to be on Channel Sliding Mechanism.
- *The contractor to follow the banks colour Coding. Any other specified colour to be superceded by the Banks Colour code.
- *All board to be BWP. Of approved brand and if written BWR it should be superceded by BWP board/ply.

S.No.	Description of item	Unit	Qty.	Rate	Amount
1	Main Door with Fixed Aluminium Glazing Powder coated of Bank colour coding. Door Size-4'-0" X 7'-0" Frame- 6"X2" Aluminium powder coated frame (18 gauge) (All four sides) with approved colour Bank's Engineer/Architect Glass 5.0/ 6.0mm thick Plane glass with mat film as approved by architect/bank engineer) Floor Spring-Heavy Duty appropriate size (Hyper/Everite make) Handle-'D' Type stainless steel finish both sides with push/pull indication)	Sq.ft.	70.00		
2	Branch Manager Table with Side Table. Size -5'-0" (L) X 2'-6" (W) X2'-6" (H) Providing and placing in position table made of phenol bonded 19mm thick commercial board with top front and sides finished in 1.0 mm Thick laminate and 12mm thick toughened glass on top. The front facade of the table to have 6 mm thick and 29 mm wide moulding. Every table shall be provided with a key board, drawer, and a cabinet with a shutter below W-375mm, H-750mm, Depth- 500mm. The storage unit shall consist of provision for C.P.U. 600X250 size Keyboard to be made of 19 mm thick commercial board and finished Drawers and a cabinet with a shutter below W-375mm, H-750mm, Depth-500mm. shall consist of 12 mm thick commercial board for bottom, sides and back of 19 mm thick phenol bonded commercial board with laminate in front and shall slide on tray system provision (sliding mechanism). All the units shall be provided with all the necessary hardware as approved by the Architect. such as knobs, handles, etc. All unexposed surfaces to have two coats of synthetic enamel paint with primer and base, all complete, specifications and directions of the engineer in charge.	Nos.	1.00		
3	Cash Cabin Partition (HT-7'-0" ONLY) Providing and fixing of Cash Enclosures at height of 7'-0" with Anodized aluminium frame work, heavy sections (2mm thickness) of 1.75"x1.75", spacing of 2'0"x2'0" on bothsides and covered 6mm thick BWP plywood finished with 1mm thick laminate of approved colour. Partition shall have provision for opening and 19mm BWP plywood tray for challan receiving purpose. Cost include aluminium grill and fixed with teak wood beading and duco paint. Cost also include 3 Nos of Solid core flush Doors with sizes of 2'6"x7'0", fixed in the partition. Door shall have teak wood beading and lipping with duco paint. Door finished with 1mm thick laminate of approved colour for skirting of approved pattern. Door shall have 8mm glass fixed with teak wood beading and duco paint. Rate to include hardware's like brass hinges, godrej three nos of night latch, door closure, door stopper and handles. Cost also include cash transaction opening shall be provided with door arrangements made with BWP plywood frame work finished by laminate, duco paint and locking system. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect. Decorative Grill (12mm thk)-hexagonal opening as per instruction of Bank's Engineer/Architect.) All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak Lipping.	Sq.ft.	165.00		
4	Cash Counter Bank counter of approved design for cashier made of 19.00 mm commercial block board and mica 1.00 mm thick of approved brand and colour on front customer top and writing desk. Height of counter from customer side 114cm (45"). width of writing desk 75cm.(30") with provision of cupboard after every 1.20 mts made of 19.00 mm block board with 1.0 mm sunmica pasted on both side (inner and outer), and teakwood beading complete with quality polish finish. Mica pasted on both sides external & internal including all locks & handles with door closer.	Rft.	5.00		
5	Front Counter Front counter made of 19.00 mm block board with table top at the height 75 cm and 80 cm wide sunmica 1.0 mm on top and cup board and sliding key board with provision of fixing of glass in front. Mica pasted on both sides external & internal including all locks & handles.	Rft.	15.00		



S.No.	Description of item	Unit	Qty.	Rate	Amount
6	Cash Cabin-Aluminium Grill Top with teak Decorative Grill Partition).	Sq.ft.	47.00		
	Providing and fixing of Aluminum grill work in cash counter top with all nessecary fixing support of 'L', 'H' and 'C' aluminium sections and etc. Cost include 'L', 'H' and 'C' aluminium sections, hardwares, tools, wastages, lead, lift, labour charges, loading, unloading charges, cutting, transport and etc. Complete as per instructions of the Architect.				
7	12 mm Glass on Front Counter & Cash Counter	Sq. ft.	50.00		
	12 mm float glass with rounded edges with etching as per the requirement of bank for Front counter (Height: 60 cms) (With teak wood frame 70 cm).				
8	Low Height Partition up to 3'-6" ht. glazed/Unglazed partition	Sq.ft.	190.00		
	Half Height partition to be made with Anodized Aluminium frame work, heavy sections (2mm thickness) of 1.75"x1.75" sections, spacing of 2'0"x 2'0" on bothsides and covered with 8mm thick BWP plywood finished with 1mm thick laminate of approved colours for skirting & borders and white colour laminates for base on both sides with all necessary fixing accessories, arrangements and etc. Partition shall be block partition till 3' ht. and 1'-6" glazing. It shall have 12mm thick etched glass and fixed with teak wood beading with melamine polish. Clear glass shall be finished with frosted film sticking over the glass of approved pattern and design. Rate to include providing cutouts and provisions to run electrical conduits, switches, etc. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect.				
9	Storage (Low/Full Height)	Sq.ft.	55.00		
	Size-2'-6" highX 1'-6" deep				
	Size-8'-6" highX 1'-6" deep				
	Ply Wood -19.0mm thick board for side top and door & back 6.0mm IS 303 with shutters, shelf 19.0mm ply				
	Shelf-19.0mm thick MR Grade IS303 ply				
	Handle-Brush finish stainless steel				
	Lock-Vijayan/Godrej				
	Internal surface zinc oxide polish and other required accessories instructed by Bank's Engineer / Architect.				
10	Column / Wall Panelling (Meter Boxing with proper locking system, 2 nos. of air-con louvers & all necessary accessories)	Sq.ft.	120.00		
	Column Panelling 8'-6" /Wall Panelling 3'-6" only considered with Anodized Aluminium frame work, heavy sections (2mm thickness) of 1.75"x1.75", spacing of 2'0"x2'0" on bothsides and covered with 6mm thick BWP plywood finished with 1mm thick laminate colours for skirting & borders, Rate to include providing cutouts and provisions to run electrical conduits, switches, etc. Cost include necessary hardwares like clamps, screws and etc. Cost include provisions for electrical db closing 19mm BWP plywood door arrangements,wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect.				
	Meter Boxing (Only front face to be measured for payment purpose) Size 3'-6" x 4'-6"				
11	Notice Baord	No.	1.00		
	Notice Board made of 19.00 mm board (size: 3'-0"x3'-0") laminated sides andcovered by good quality Cherry Colour Velvet with attached Cheque Writing Desk (6"x6"x9")-with attached Two Battens for Support, Sunmica Pasted on all sides.				
12	Writing Desk Including Suggestion Box and Cheque Drop Box	No.	1.00		
	Writing ledge of 19 mm Phenol bonded board as/design on 19 mm thick with pockets for slips of 6mm glass machine polished with seperators completed to the satisfaction of the architect and the Drawing. The Writing ledge includes a Suggestion box below, cheque drop box and a notice board above complete to the satisfaction of the Architect.				
13	Hydraulic Door Closure. (to be Godrej)	No.	1.00		
	Providing and fixing of hydraulic door closure (Make-Godrej, Product Code-4539 or equivalent) for doors. It shall incorporate the following –				
	- Body manufactured from Aluminium extruded alloy machined to extreme accuracy.				
	- Rack and Pinion-made of machined alloy steel duly heat-treated.				
	- Adjustable closing speed.				
	- Suitable for right hand and left hand opening doors.				
	- Suitable for door / frame mounting.				
	- Suitable for door weight up to 60 kgs.				
	- Suitable for 180 / 100 degree door opening.				
	- All complete to the satisfaction of the Architect.				



S.No.	Description of item	Unit	Qty.	Rate	Amount
14	False Ceiling Works (Gypsum)	Sqft	580.00		
	Supplying and Erecting Saint Gobain Gyproc Gypboard false ceiling at different heights with saint gobain framework of G.I.Section (of medium thickness) of spacing 4'0"x2'0" above with 12.5 mm gypboard shall be fixed with all necessary fixing accessories, arrangements and etc. Rate shall include cut-outs for lights, ac and etc. The ceiling shall be putty finished and sanded to form clean and homogeneous surface. Cost include hidden lighting arrangements and etc. Rate to include painting two coats of acrylic emulsion of approved colour after necessary preparation, one coat of primer, full putty and tc. Cost include all necessary hardwares like nails, screws, wastages, transports, loading, unloading charges, labours, lead, lift, materials, tools and etc. Complete as per drawings and instructions of the Architect.				
15	False Ceiling (Armstrong)	Sqft	312.00		
	False ceiling - 2 Grid false ceiling- Providing and fixing Saint gobain tile Grid ceiling of (GYPROC SAINT-GOBAIN Mineral fiber ceilings of 'CELOTEX PIN' board with "Narrow Reveal edge Corner bevel" 14mm grid (Bolt Slot) section) and (ARMSTRONG "CLASSIC LITE RH99" tile with "BEVELLED TEGULAR Suprafine 15 mm /Silhouette grid section) in aluminium powder coated sections supported from ceiling (4'0"x4'0" grid for support rods) with necessary GI framework of every 2'0"x2'0" grid junction, proper levelling and finished of the joints & top surface as per manufactures specifications and all accessories, arrangements and etc. All edges shall be perfectly straight. Tile shall be carefully laid with neat arrangements like hand gloves and etc. Cost include replacement of damaged or stained tile. Cost include all necessary hardwares like nails, screws, wastages, transports, loading, unloading charges, labours, lead, lift, materials, tools and etc. Complete as per drawings and instructions of the Architect. MAKE- SAINT GOBAIN and ARMSTRONG.				
	Total				

Note: All rates are excluding G.S.T.



Estimate for Electrical and AC piping works for Baroda U.P. Bank

Branch at Mugisapur

Region - Kanpur Dehat

S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE	AMOUNT
1	SITC of 100Amp Kit kat Fuse unit neutral link on wooden board (3' x 3') complete with connections (new).	1.00	Set		
2	ELECTRICAL DISTRIBUTION Db SITC of 6way Vertical TPN DB complete with 100Amp 16kA TPN MCCB as Incomer, 63A TP 10kA MCB -4 Nos and 6-16Amp S.Pole 10kA MCB-3 Nos as outing complete in all respects as required The job shall be completed, to the satisfaction of the Bank Engineer/Architect.	1.00	Set		
3	<i>Changeover</i> . S/F of 63A 4P changeover near Main Db for regulating DG supply including proper connections.	1.00	Each		
LOM	Changeover Switch- C&S/ Havells/ L&T/ HPL				
2	UPS I/P, O/P AND DISTRIBUTION				
a.	SITC of 40/32 AMP industrial socket along with DPMCB for UPS & Inverter I/P	2.00	Nos.		
b.	SITC of 20AMP industrial socket along with MCB for UPS & Inverter O/P	2.00	Nos.		
c.	SITC of 12 WAY SPN DB Double Door (1 No. 40 AMP DP MCB and 10 NOS. 6-10 AMP SPMCB) (Branch UPS Power Distribution for UPS Points at CCTV System in BM Cabin (2nos.), F&B Alarm System (2nos.) and 9U Rack(2nos.), and Staff counters (2nos.).	1.00	Nos.		
d.	SITC of 63Amp Rotary Phase selector switch complete with RYB indication light in incloser complete in all respects as required. (Branch UPS)	1.00	Nos.		
3	RAW POWER & FAN, LIGHTING DB & AC DISTRIBUTION BOARD				
a.	4 WAY TPN DB Double Door (1 No. 20 AMP TP MCB and 12 Nos. 6-10 AMP. SPMCB in each outgoing circuit for Light, Fan & 6A Socket 15A Power Points, Ac points) all complete.	1.00	Nos.		
4	B - AIR CONDITIONING				
a.	AC Point: Providing AC points with circuit wiring with 3*4sq.mm FRLSH Cu stranded wires to be laid in 20mm PVC medium concealed in wall/ floor/ panelling/ partitions as per requirement. The work shall include S/F of MCB protected power unit for AC c/w 40A 2P MCB including proper connections. The job shall be complete & to the entire satisfaction of the Bank.	3	Point		
	PVC Insulated FRLSH Copper wire (ISI Marked)- Skyline/ Finolex/ Havells/ Polycab				
	PVC Conduit- CAP/ BEC/ Sieko/ AKG				
	MCB Protected Power unit c/w 10kA MCB "C"- Havells/ L&T/ Siemens/ Schneider				
b.	Wiring with 3*4.0sq.mm FRLSH stranded Cu. wires laid in 20mm OD PVC/ flexible pipe heavy duty laid on floor & concealed in wall/ floor as per requirement to various voltage stabilizers. The job includes making connections at both ends with proper size of lugs to the entire satisfaction of the Bank.	18	Mtr.		
	PVC Insulated FRLSH Copper wire (ISI Marked)- Skyline/ Finolex/ Havells/ Polycab				
	PVC Conduit- CAP/ BEC/ Sieko/ AKG				
5	CABLES				
a.	SITC of 3.0 Core 25.0 Sq.mm Aluminium Armoured Cable (From Electric Meter to Electric Panel), complete with end termination and all respect as required.	18.00	Mtr.		



S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE	AMOUNT
b.	SITC of 4 x 6.0 Sq.mm Copper Wire + 1 x 4.0 Sqmm Copper Earth Wire (Panel to UPS Incomer, LDP, AC and UPS DB) in PVC Pipe fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio and painting compete with end termination/lugs and in all respect as required.	65.00	Mtr.		
c.	SITC of 2 x 6.0 Sq.mm Copper Wire + 1 x 2.5 Sqmm Copper Earth Wire (Rotary Switch to UPS and UPS to UPS DB) in PVC Pipe fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio and painting compete with end termination/lugs and in all respect as required.	75.00	Mtr.		
6	EARTHING				
a.	PIP technology GEL type 50mm dia 3000mm long earth electro. One Earthing for Neutral grounding,	2.00	Nos.		
b.	4 Sq.mm Copper Earth Wire from earthing pit /Earth terminal to load point (UPS DB and Main DB etc)	45.00	Mtr.		
7	UPS POINT				
a	Supply & Installation of point wiring for Primary UPS or stabilized power plug points on workstations / table for computers using 3 x 1.5 Sq.mm copper conductor multi strand FR PVC sheathed flexible wire pulled through floor raceways/conduit and taken upto table top using PVC rigid or flexible conduits run within wooden/metal partitions. Each point consisting of 2 nos of 10A 3 pin sockets, 1 nos 16A 2/3 pin sockets, 1 nos 16A Switch (Modular) & 1 nos indicator, wired together forming one point. The earth wire of green color only. No secondary UPS Points to be made.	9.00	Nos.		
8	RAW POWER POINT 16A SOCKET POINT IN WALL ONLY				
a.	Supply & Installation of point wiring for Primary Raw power plug points on walls only for computers using 2X4+1X2.5 Sq.mm copper conductor PVC sheathed flexible wire pulled through already laid floor raceways and taken upto table top using PVC rigid or flexible conduits run within wooden/metal partitions. Each point consisting of 2 nos of 16A 2/3/5 pin socket & 2 nos 16A Switch (Modular), wired together forming one point. The earth wire of green color only. No secondary Points to be made. (Only 1cash, 2B.M. 3Officer, 1router)	7.00	Nos.		
b	Strong room controlling DP MCB - Circuit wiring with 3*1.5sq.mm FRLSH Cu stranded wires to be laid in 20 mm OD PVC medium duty laid & concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The job also includes supply & fixing of 32A 2P MCB in 2way metallic box including connections with lugs. The job shall be complete & to the entire satisfaction of the Bank.	1.00	Job		
	PVC Insulated FRLSH Copper wire (ISI Marked)- Skyline/ Finolex/ Havells/ Polycab				
	PVC Conduit- CAP/ BEC/ Sieko/ AKG				
	MCB 10kA "C" Characteristics L&T/ Siemens/ Schnider/ Legrand				
9	LIGHT/FAN POINT				
a.	Supply & Installation of concealed point wiring using 600v grade 1.5 Sq.mm copper conductor PVC insulated wires (with proper R,Y,B color code) pulled through heavy gauge PVC conduits laid concealed over false ceiling including 2 Nos. 2.5 sqmm circuit wires from the relevant DB and also including 2.5 sqmm green color copper earth wire and switch plate, switches, etc. as approved by the Bank's Engineer/Architect.	44.00	Nos.		



S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE	AMOUNT
b.	Secondary light points looped from the primary point (For Down Lights & Tubelights only, Two downlights from one point)	15.00	Nos.		
c.	Ceiling Fan Point including the cost of 10A modular Switch along with 4/5 step electronic fan regulator.	5.00	Nos.		
d.	Wall Fan Point along with 10 AMP modular switch	7.00	Nos.		
e.	Exhaust Fan Point along with 10 AMP modular switch	2.00	Nos.		
f.	6/10A Switch with 5pin 10A socket in counter, light & fan board	7.00	Nos.		
10	DATA CABLING & POINT THERE MUST BE MINIMUM 3FEET DISTANCE BETWEEN DATA AND				
	Supplying and laying of D-Link make CAT-6 (UTP) cable through trenches / conduits.				
a.	Supplying and laying D-link make CAT-6 Cable complete with CAT-6 information outlet with plate & surface Box at individual Tables.	8.00	Nos.		
b.	Supplying and fixing of 2 mtr long crimped patch cord	8.00	Nos.		
e.	SITC of 9U Rack including wire manager, power supply card, hardwares etc. complete in all respects.	1.00	No.		
11	FIXTURES				
	SITC of following fixtures as per make list				
a.	LED Square Light (2' x 2') fitting (white) - 36 Watts Philips LED Recessed Panel Light Square 36W (RC370B LED30S-6500)	20.00	Nos.		
b.	LED Down Lighter (white) - 9 Watts Philips Aura Style Edge 10w Led Downlighter, (Round Recessed Thin Trim, 47mm)	15.00	Nos.		
c.	LED Tube Light Patti Type (white) - 20 Watts Make/ Brand as per MAKE LIST	8.00	Nos.		
d.	Ceiling Fan - 1200mm Make/ Brand as per MAKE LIST	5.00	Nos.		
e.	Wall Mounted 80/100 watt plastic body Fan - 400mm, 1300 to 1500RPM Make/ Brand as per MAKE LIST	7.00	Nos.		
f.	Exhaust Fan Metal Body - 300mm Make/ Brand as per MAKE LIST	2.00	Nos.		
g.	LED Bulb with holder (white) - 9 Watts	2.00	Nos.		
	TOTAL (A)				
ESTIMATE FOR AIR- CONDITIONING PIPING WORKS					
1	Drain Water Piping Constructed out of PVC Hard Pipes, fitting, accessories, bends, elbows, tees, hanger, support, anchors, ISI approved Finolex/Prince Make (32mm)	RM	50.00		
2	Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton, 1/2 and 1/4 Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube and S.I.T.C. of 12.5 Sq.mm. & 6.25 Sq.mm. dia. Copper refrigerant pipe with foam Insulation between Indoor & Out door units with breaking of wall for making hole wherever required For Split Air- Conditioners. And S.I.T.C. of 19 mm dia & 16 mm dia Copper Refrigerant Pipes with Foam insulation between Indoor & Out door units. with breaking of wall wherever required for 2-3 Tr Cassette/ Inverter Air conditioners.	Rm	75.00		
3	S.I.T.C. of 4 core Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above	Rm	75.00		
	TOTAL (B)				
	GRAND TOTAL (A+B)				

Note: All rates are excluding G.S.T.



Abstract of Cost for Baroda U.P. Bank		
Branch at Mugisapur		
Region - Kanpur Dehat		
S.No.	DESCRIPTION	AMOUNT (Rs.)
1	FURNISHING WORKS	
2	ELECTRICAL AND A.C PIPING WORKS	
	TOTAL (Rs.)	
Note: All rates are excluding G.S.T.		

